

From: "Anne Zareh" <anne.zareh@braziermotti.com.au>
Sent: Wed, 29 Jul 2026 16:50:36 +1000
To: "Development Assessment" <developmentassessment@townsville.qld.gov.au>
Cc: "Jayne Carter" <jayne.carter@townsville.qld.gov.au>; "Dale Armbrust" <dale.armbrust@townsville.qld.gov.au>
Subject: MCU26/0040 - Further Advice Assessment Manager- 13 Market Street BURDELL
Attachments: FA Response.pdf

Hi Jayne,

Reference is made to Council's Further Advice dated 10 July 2026. Please find attached the applicant's formal response.

Further, we anticipate lodging a response to SARA's information request by the end of this week. For completeness, I will provide Council with a copy of the response once it has been submitted.

Kind regards
Anne



Anne Zareh
Associate/Senior Town Planner

P 07 4772 1144
M 0416 486 309

595 Flinders St
Townsville Q 4810

braziermotti.com.au



The information transmitted is intended only for the person or entity to which it is addressed and may contain confidential and/or privileged material. Any review, retransmission, dissemination, or other use of, or taking of any action in reliance upon, this information by persons or entities other than the intended recipient is prohibited. If you received this in error, please contact the sender and delete the material from any device.

From: Development Assessment <developmentassessment@townsville.qld.gov.au>
Sent: Friday, 10 July 2026 12:09 PM
To: Anne Zareh <anne.zareh@braziermotti.com.au>
Cc: Jayne Carter <jayne.carter@townsville.qld.gov.au>; Dale Armbrust <dale.armbrust@townsville.qld.gov.au>
Subject: MCU26/0040 - Letter - Further Advice Assessment Manager- 13 Market Street BURDELL

Your Reference: 25544-190-1

Good afternoon,

Please find attached an electronic copy of the above mentioned.

If you have any questions please don't hesitate to contact the Assessing Officer Jayne Carter, on 4727 9428.

If you would like to follow the progress of your application online, please click on [Launch ePlanning](#) to access.

Kind regards,

**Planning & Development
TOWNSVILLE CITY COUNCIL**

Discover everything you need to undertake planning and development in Townsville, visit [Planning - Townsville City Council](#)

P 4417 5325 **E** developmentassessment@townsville.qld.gov.au

103 Walker Street, Townsville QLD 4810 | PO Box 1268, Townsville QLD 4810



OUR VISION - A globally connected community driven by lifestyle and nature **OUR PURPOSE** - Grow Townsville

WINNER QLD TRAINING AWARDS NQ REGION LARGE EMPLOYER OF THE YEAR 2022 & 2023

Townsville City Council acknowledges the Wulgurukaba of Gurambilbarra and Yunbenun, Bindal, Gugu Badhun and Nywaigi as the Traditional Owners of this land. We pay our respects to their cultures, their ancestors and their Elders, past, present, and all future generations.



PRIVACY AND CONFIDENTIALITY NOTICE >> The information contained in this email is intended for the named recipients only. It may contain privileged and confidential information and if you are not the named intended recipient, you must not copy, distribute or take any action in reliance on it. If you have received this email in error, please notify us immediately by email or the telephone number or email listed above. ***** Please consider the environment before printing this email *****

Date 29/07/2026

Josh Lean
Oreana Property
Level 17, 627 Chapel Street
South Yarra, Victoria, 3141
Via email: joshl@oreana.com.au

Dear Josh

Response to Further Advice – P004169 (MCU26/0400)

In response to Council's comments regarding the predicted 1% AEP afflux (100–200 mm) within Market Street east of the development site, we note the following.

Market Street was originally designed to accommodate runoff from the subject development area. As shown on the approved stormwater catchment plan (Drawing STG004/85), Market Street forms part of the intended drainage network for Catchments T, U and V. These catchments are broadly consistent with the contributing catchment identified in Figure 2.5 of the Flood Impact Assessment.

Accordingly, the conveyance of runoff through Market Street is not a new consequence of the proposed development, but rather an outcome that was anticipated and incorporated into the approved drainage design.

The afflux identified within the Flood Impact Assessment was therefore expected. Our review indicates that Council's flood model does not fully account for the existing approved drainage infrastructure and overland flow arrangements within Market Street. As a result, the model does not accurately represent the hydraulic behaviour intended under the approved stormwater design.

Accordingly, the identified afflux is considered to reflect limitations in the representation of the approved drainage infrastructure within the underlying flood model rather than an adverse flooding impact caused by the development.

On this basis, we consider that additional mitigation measures are not warranted, as the approved drainage network already provides for the conveyance of runoff from the contributing catchments and the development does not materially alter the intended flood conveyance function of Market Street.


Yours sincerely,



Adam Pease RPEQ

Senior General Manager – North | Principal Civil Engineer

Attachment: Drawing STG004/85



CATCHMENT DATA

Catchment	Area (ha)	C50	EIA (ha)
A	0.172	0.92	0.158
B	0.075	0.92	0.069
C	0.350	0.92	0.322
D	0.354	0.92	0.326
E	0.295	0.92	0.271
F	0.254	1.00	0.254
G	1.783	1.00	1.783
H	0.814	1.00	0.814
I	0.164	1.00	0.164
J	0.443	1.00	0.443
K	0.941	1.00	0.941
L	0.078	1.00	0.078
M	0.334	0.92	0.307
N	0.215	1.00	0.215
T	2.246	1.00	2.246
U	3.380	1.00	3.380
V	3.755	1.00	3.755
W	0.240	1.00	0.240
X	0.213	1.00	0.213
Y	0.073	1.00	0.073
Z	0.219	1.00	0.219

Q50 CATCHMENT PLAN

SCALE 1:2000

REAL PROPERTY DESCRIPTION:

LOT 1 on RP835468 & LOT 94 on SP143119

REV	DATE	REVISIONS	REC.	APPR.
D	15/02/10	MAJOR DESIGN AMENDMENTS		
C	04/11/09	AMENDMENTS TO ROAD Q		
B	10/11/08	ISSUED FOR CONSTRUCTION		
A	15/08/08	ISSUED FOR OPERATIONAL WORKS APPROVAL (RFI)		

This drawing is produced and remains the property of Bradmar Pty Ltd, trading as UDP Consulting Engineers. This drawing shall not be used in any manner without the prior agreement of UDP Consulting Engineers. UDP Consulting Engineers shall not accept any responsibility or liability to any third party as a result of the content contained on this drawing. The Contractor must verify all dimensions on site before commencing any work or making any shop drawings. Figured dimensions must be used in preference to scaled dimensions. All scaled dimensions must be verified on site.

DRAWN:
C.MELLIHAN
DESIGNED:
G.PARKER
CHECKED:
D.BOYCE
PROJECT MANAGER:
D.BOYCE
XREF: STG004-XR

DATUM: AHD (DERIVED)
PSM 131700
RL.11.714
BRUCE HIGHWAY
PROJECT DIRECTOR:
P.BRADY
RPEQ 7112

UDP Consulting Engineers
Urban Development Design Infrastructure Project Management
Suite 3, 62 Walker St
TOWNSVILLE QLD 4810
PO BOX 1110
TOWNSVILLE QLD 4810
Phone: (07) 4772 0666
Fax: (07) 4772 0566
Email: main@udpconsulting.com.au

STOCKLAND DEVELOPMENT PTY LTD

NORTH SHORE PRECINCTS 2 & 3 - STAGE 201

BRUCE HIGHWAY, BURDELL

Q50 STORMWATER CATCHMENT PLAN

DRAWING SIZE	SCALE	DRAWING NO.	REV
A1	1:2000	STG004/85	D

Q5 - DATA TABLE

Design Point	Contributing Catchments	EIA ha	Tc mins	l ₅₀ mm/hr	Q ₅₀ m ³ /s	Q ₅ PIPES AT X _m /s Ø mm	Q ₅₀ m ³ /s	VELOCITY X _m /s	NOTES
1	A	0.158	1.5	362.8	0.159	-	0.000	0.159	-
2	C	0.322	14.9	196.8	0.176	-	0.000	0.176	-
3	B	0.069	1.1	357.8	0.069	-	0.000	0.069	-
4	1 + 2 + 3	0.549	14.9	196.8	0.300	-	0.000	0.300	-
5	4 + D	0.875	16.9	186.9	0.454	-	0.000	0.454	-
6	5	0.875	16.9	186.9	0.454	-	0.000	0.454	-
7	6 + E	1.146	18.9	178.1	0.567	-	0.000	0.567	-
8	23 + F	1.293	11.9	215.4	0.773	-	0.000	0.773	-
9	G	1.783	7.4	257.7	1.277	825	0.374	0.902	0.7
10	9	1.783	7.4	257.7	1.277	900	0.445	0.831	0.7
11	10 + H	2.597	9.5	234.7	1.693	1050	0.606	1.087	0.7
12	11	1.558	9.5	234.7	1.016	825 + 1050	0.980	0.036	0.7
13	12 + I	1.722	10.6	225.7	1.080	825 + 1050	0.980	0.100	0.7
14	13	1.722	10.6	225.7	1.080	-	0.000	1.080	-
15	14 + J	2.165	12.9	208.6	1.255	-	0.000	1.255	-
16	K	0.941	5.1	289.5	0.757	-	0.000	0.757	-
17	15 + 16	3.106	13.0	208.2	1.796	-	0.000	1.796	-
18	17 + L	3.184	14.2	200.6	1.774	-	0.000	1.774	-
19	M	0.307	12.5	211.7	0.181	-	0.000	0.181	-
20	18 + 19	3.491	14.2	200.6	1.945	-	0.000	1.945	-
21	20 + N	3.706	15.9	191.6	1.972	-	0.000	1.972	-
22	7 + 8	2.439	18.9	178.1	1.207	-	0.000	1.207	-
23	11	1.039	9.5	234.7	0.677	-	0.000	0.677	40% SPILFLOW
42	T	2.246	9.800	232.3	1.450	825Ø+1050Ø	1.400	0.049	1.0
43	42	2.246	9.800	232.3	1.450	1050Ø+1200Ø	1.398	0.052	0.7
44	43+U	5.626	11.417	219.1	3.425	1050Ø+1200Ø	1.997	1.428	1.0
45	44	5.626	11.417	219.1	3.425	2x1200Ø	2.262	1.163	1.0
46	45+V	9.381	13.117	207.4	5.405	2x1200Ø	2.262	3.143	1.0
47	46(50%)	4.691	13.117	207.4	2.702	1500	1.767	0.935	1.0
48	47+W	4.931	14.300	200.2	2.742	675	0.358	2.385	1.0
49	48	4.931	14.300	200.2	2.742	600x300RCBC	0.126	2.616	1.0
50	X	0.213	1.367	363.2	0.215	-	0.000	0.215	-
51	50	0.213	1.367	363.2	0.215	600x300RCBC	0.126	0.089	0.7
52	49+51+Y	5.217	16.133	190.4	2.759	525	0.152	2.608	0.7
53	52+Z	5.436	17.817	182.6	2.756	-	0.000	2.756	-

LEGEND:

- CATCHMENT BOUNDARY
- Ⓐ DENOTES CATCHMENT NAME
- 24 DENOTES DESIGN POINT
- ⇨ DIRECTION OF FLOW

0 40.0 80.0 120.0m
SCALE 1: 2000