SC6.4.5 Construction management

- (1) This section outlines the standards and provides advice and guidelines for construction management of development and covers pre-construction, construction and quality management systems.
- (2) All development works shall be supervised by a Registered Professional Engineer of Queensland with relevant experience. Where the owner or developer does not have such a Professional Engineer in their employ, a Registered Consulting Professional Engineer shall be retained for the purpose of supervising the development works prior to commencement of work.
- (3) This section aims to clearly define the role of council, Superintendent, Consultant, Principal Contractor and the Developer. This section seeks to ensure that inherited development works are constructed to achieve a cost effective operation and maintenance asset and perform adequately for their design lives.
- (4) Reference and source documents
 - (a) Development manual planning scheme policy sub-sections to be read and applied in conjunction with this policy sub-section are as follows:
 - SC6.4.6.1 Water sensitive urban design construction and establishment guidelines
 - SC6.4.6.2.5 Pipeline testing and restoration (Water supply sub-section)
 - SC6.4.6.3.4 Pipeline testing and restoration (Sewerage system sub-section)
 - SC6.4.6.19 Stabilisation
 - SC6.4.6.22 Pavement markings

<i>a</i> .	SC6.4.6.29 Boundary fencing SC6.4.6.30 Control of traffic	
(b)	Australian Standards AS 1012.1	Methods of testing concrete - Sampling of fresh concrete
	AS 1012.3.1	Methods of testing concrete - Determination of properties related to the consistency of concrete - Slump test
	AS 1012.14	Methods of testing concrete - Method for securing and testing cores from hardened concrete for compressive strength
	AS 1012.4	Methods of testing concrete - Determination of properties related to the consistency of concrete - Compactibility index
	AS 1012.8	Methods of testing concrete - Method of making and curing concrete
	AS 1012.9	Methods of testing concrete - Determination of the compressive strength of concrete specimens
	AS 1141.11	Methods for sampling and testing aggregates - Particle size distribution
	AS 1141.12	Methods for sampling and testing of aggregates - Materials finer than 75 micrometre in aggregates (by washing)
	AS 1141.14	Methods for sampling and testing aggregates - Particle shape, by proportional caliper
	AS 1141.15	Methods for sampling and testing aggregates - Flakiness index
	AS 1141.18	Methods for sampling and testing aggregates - Crushed particles in coarse aggregate derived from gravel
	AS 1141.22	Methods for sampling and testing aggregates - Wet/dry strength variation
	AS 1141.23	Methods for sampling and testing aggregates - Los Angeles value
	AS 1141.24	Methods for sampling and testing aggregates - Aggregate soundness - Evaluation by exposure to sodium sulphate solution

AS 1141.25	Methods for sampling and testing aggregates - Degradation factor
AS 1141.25.1	Methods for sampling and testing aggregates - Degradation factor - Source rock
AS 1141.42	Methods for sampling and testing aggregates - Pendulum friction test
AS 1160	Bituminous emulsions for the construction and maintenance of pavements
AS 1289.3.2.1	Methods of testing soils for engineering purposes - Soil classification tests - Determination of the plastic limit of a soil - Standard method
AS 1289.3.3.1	Methods of testing soils for engineering purposes - Soil classification tests - Calculation of the plasticity index of a soil
AS 1289.3.6.1	Methods of testing soils for engineering purposes - Soil classification tests - Determination of the particle size distribution of a soil - Standard method of analysis by sieving
AS 1289.3.7.1	Methods of testing soils for engineering purposes - Soil classification tests - Determination of the sand equivalent of a soil using a power-operated shaker
AS 1289.4.2.1	Methods of testing soils for engineering purposes - Soil chemical tests - Determination of the sulfate content of a natural soil and the sulfate content of the groundwater - Normal method
AS 1289.4.3.1	Methods of testing soils for engineering purposes - Soil chemical tests - Determination of the pH value of a soil - Electrometric method
AS 1289.4.4.1	Methods of testing soils for engineering purposes - Soil chemical tests - Determination of the electrical resistivity of a soil - Method for sands and granular materials
AS 1289.5.1.1	Methods of testing soils for engineering purposes - Soil compaction and density tests - Determination of the dry density/moisture content relation of a soil using standard compactive effort
AS 1289.5.4.1	Methods of testing soils for engineering purposes - Soil compaction and density tests - Compaction control test - Dry density ratio, moisture variation and moisture ratio
AS 1289.5.5.1	Methods of testing soils for engineering purposes - Soil compaction and density tests - Determination of the minimum and maximum dry density of a cohesionless material - Standard method
AS 1289.5.7.1	Methods of testing soils for engineering purposes - Soil compaction and density tests - Compaction control test - Hilf density ratio and Hilf moisture variation (rapid method)
AS 1289.5.8.1	Methods of testing soils for engineering purposes - Soil compaction and density tests - Determination of field density and field moisture content of a soil using a nuclear surface moisture—Density gauge - Direct transmission mode
AS 1289.6.1.1	Methods of testing soils for engineering purposes - Soil strength and consolidation tests - Determination of the California Bearing Ratio of a soil - Standard laboratory method for a remoulded specimen
AS 1432	Copper tubes for plumbing, gasfitting and drainage applications
AS 1477	PVC pipes and fittings for pressure applications

AS 1478	Chemical admixtures for concrete, mortar and grout
AS 1580.107.3	Paints and related materials - Methods of test - Determination of wet film thickness by gauge
AS 1741	Vitrified clay pipes and fittings with flexible joints - Sewer quality
AS 1742.3	Manual of uniform traffic control devices - Traffic control for works on roads
AS 2008	Bitumen for pavements
AS/NZS 2032	Installation of PVC pipe systems
AS 2129	Flanges for pipes, valves and fittings
AS 2280	Ductile iron pipes and fittings
AS 2150	Hot mix asphalt - A guide to good practice
AS 2544	Grey iron pressure fittings
AS 2638	Gate valves for waterworks purposes
AS 2758.1	Aggregates and rock for engineering purposes - Concrete aggregates
AS 2891.9.3	Methods of sampling and testing asphalt - Determination of bulk density of compacted asphalt - Mensuration method
AS/NZS 1477	PVC pipes and fittings for pressure applications
AS 3439	Low-voltage switchgear and controlgear assemblies
AS 3582.1	Supplementary cementitious materials for use with portland and blended cement - Fly ash
AS 3583.1	Methods of test for supplementary cementitious materials for use with portland and blended cement - Determination of fineness by the 45 micrometre sieve
AS 3583.12	Methods of test for supplementary cementitious materials for use with portland cement - Determination of available alkali
AS 3583.13	Methods of test for supplementary cementitious materials for use with portland cement - Determination of chloride ion content
AS 3583.14	Methods of test for supplementary cementitious materials for use with portland cement - Determination of insoluble residue content
AS 3583.2	Methods of test for supplementary cementitious materials for use with portland cement - Determination of moisture content
AS 3799	Liquid membrane-forming curing compounds for concrete
AS/NZS 3905.12	Quality system guidelines - Guide to AS/NZS ISO 9001 for architectural and engineering design practices
AS 3952	Water supply - Spring hydrant valve for waterworks purposes
AS 3972	General purpose and blended cements
AS 4198	Precast concrete access chambers for sewerage applications

AS 4373 Pruning of Amenity Trees

AS/NZS 4455 Masonry units, pavers, flags and segmental retaining wall units

AS 4687 Temporary Fencing and Hoardings

AS 4970 Protection of trees on development sites

AS 5101.4 Methods for preparation and testing of stabilized materials - Unconfined

compressive strength of compacted materials

AS/NZS ISO 9001 Quality management systems - Requirements

AS ISO 10006 Quality management systems - Guidelines for quality management in

projects

AS ISO 10006 Quality management systems - Guidelines for quality management in

projects

AS ISO 10013 Guidelines for quality management system documentation

(c) Department of Transport and Main Roads

Standard specifications roads

MRTS17 - Bitumen

MRTS18 - Polymer Modified Binder

MRTS21 - Bituminous Emulsion

MRTS22 - Supply of Cover Aggregate

MRTS30 - Dense Graded and Open Graded Asphalt

Materials testing manual

Q103A Particle size distribution (wet sieving)

Q104A - Liquid limit (cone penetrometer)

Q104D - One-point liquid limit (cone penetrometer)

Q105 - Plastic limit and plasticity index

Q113A - California bearing ratio (standard compactive effort)

Q115 - Unconfined compressive strength of compacted materials

Q142A - Dry density- moisture relationship (standard compaction)

Q201 - Flakiness index

Q205B - Ten percent fines value (wet)

Q205C - Wet/dry strength variation

Q208A - Degradation factor (source rock)

(d) Other

ASTM International, ASTM-D 2434-68 - Standard Test Method for Permeability of Granular Soils (Constant Head)

Environmental Protection (Noise) Policy (EPP (Noise))

International Erosion Control Association, Best Practice Erosion and Sediment Control Document (BPESC)

NSW Department of Transport, Roads and Maritime Services (RMS), *Test method T432: Rate of slaking of quicklime, October 2012*

TCC-001

Work Health and Safety Act 2011

SC6.4.5.1 Pre-construction guidelines

SC6.4.5.1.1 Pre-construction steps

The chart presented below indicates the steps required to be undertaken prior to commencement of works.



(1) Notice to commence works

The Developer must give council's Development Assessment Unit (DAU) notification of at least 5 business days (in writing) of their intention to commence construction works. Refer to SC6.4.5.1 Attachment A Development works – notice to commence works. Refer to the Development works - notice to commence works form for a list of requirements to be submitted prior to or at the pre-start meeting.

(2) Pre-start meeting

The nominated Consultant must ensure that a pre-start meeting is conducted on the premises between the contractor, supervising engineer (RPEQ), the design consultant and council representatives. This meeting represents a hold point and works may not proceed until the meeting is held and any further requirements identified during the course of the meeting have been satisfied. The pre-start meeting must be based on an agenda which includes:

- introduction of the principal contractor, supervising engineer (RPEQ), design consultant (including any specialist) and council representative. A statement of their respective roles and relevant personnel contact details must also be tabled and distributed at that meeting;
- (b) confirmation that all relevant statutory permits/approvals have been obtained;
- (c) evidence of current public liability insurance. Refer to SC6.4.5.2(21) Insurance and indemnity;
- (d) review and discussion of all relevant conditions of the development approval;
- (e) review and confirmation of the site establishment and access arrangements including all necessary site security fencing and signage requirements;
- (f) review and discussion of the approved traffic management plan and haulage routes if applicable;
- (g) review and discussion on a schedule of "hold-points" to be adopted throughout the construction phase.

 This schedule of "hold-points" is to be approved by council prior to construction proceeding;
- (h) discussion of site specific workplace health and safety issues and an approved work method statement and safety plan in compliance with the *Work Health and Safety Act 2011*;
- (i) review of the approved erosion and sediment control plan including site base stormwater management

- plans and sediment controls during and post construction. Refer to SC6.4.5.2(11) Erosion and sediment control and SC6.4.3.8 Stormwater quality management plans for further details regarding this requirement;
- (j) location confirmation and identification of all existing public utilities, services and council assets if applicable, including any approved demolition/rectification actions if required;
- (k) scheduling and identification of all necessary responsible persons to undertake any council required works (e.g. disconnection of irrigation systems, sewer line connections etc.);
- (l) review of the vegetation protection plan if applicable and confirmation that any necessary vegetation protection measures are in place;
- (m) construction schedule and program and any other details that requires review before construction work commences e.g. work quality plan and/or quality manual review of quality requirements (SC6.4.5.3 Quality management system) and inspection test plan requirements;
- (n) if required, a development notice (project sign in accordance with SC6.4.5.2.1(6) Development notice) is to be erected;
- (o) confirmation of possession of site by the contractor; and
- (p) any other relevant matters specified by the principal contractor, supervising engineer (RPEQ), consultant/s and/or council representative that may be pertinent to the successful completion of the project.

SC6.4.5.1 Attachment A Development works - notice to commence works form

Click here to view SC6.4.5.1 Attachment A Development works - notice to commence works form

Note—this form is to be completed, signed and submitted to council by the developer at least 10 working days prior to commencement of any development works.

SC6.4.5.2 Construction

SC6.4.5.2.1 General standards and guidelines

The following are general standards and guidelines during the construction of development works:

(1) Superintendent

The superintendent is to be nominated or appointed by the supervising engineer (RPEQ) and must be supervised by the RPEQ at all times throughout the construction period. The supervising engineer (RPEQ) is to take full responsibility for all construction work on the development site.

(2) Hours of work

Unless otherwise approved by council (in writing), works involving machinery of any description shall only be carried out on site from 6.30am to 6:30pm Monday to Saturday, subject to legislative requirements. No construction work is to take place on Sundays and public holidays without prior approval. Construction work includes deliveries to the site of the works and the onsite servicing of equipment.

(3) Relocation/alteration and repair to existing utility services

The location and level of all existing public utilities and services and the alignment for any new service utility or service in association are to be identified_with the relevant authority or council asset owner. The developer is responsible for any relocation and/or alteration to any public utility installation required as a result of any works carried out in connection with this development at no cost to council.

The contractor is to ensure that utmost care is to be exercised during the progress of the development works to prevent damage to any existing utility or service. Any damage to existing utilities or services directly resulting from the development works shall be the responsibility of the developer.

(4) Provision for traffic management

No works shall be conducted within an existing public road without approval (i.e. Road work permit). Any proposed road closure (partial or full), or traffic diversion is to be presented (with full details of proposed traffic management) for approval. Proposed traffic management is to comply with the relevant sections of SC6.4.6.30 Control of traffic.

The developer is to ensure that all appropriate approvals and permits are obtained from council for work zones, gantries and scaffolding prior to commencement of construction.

The developer shall be held responsible for implementing the approved traffic management plan including the safety of all vehicles, pedestrians and cyclists and must provide all necessary measures to prevent any accident, damage and loss.

(5) Condition of entry to adjoining properties

The developer or its representative must effectively protect all adjoining properties against any loss, damage or injury that may occur as a result of development works.

Works must not be undertaken on adjoining properties without prior written consent of the lawful owner. All adjoining property which has been disturbed as a result of the development shall be reinstated to a finish similar to its pre-development state or to an alternative state agreed to in writing by the affected property owner.

Upon completion of the development works, written approval from any affected property owners will be required by council prior to acceptance of the completed development works.

(6) Development notice

Where required, a project sign is to be erected within the site boundaries on the road frontage of the subject site or any other council approved location that is prominent and visible to the public. The developer is responsible for maintaining the signage for the duration of the construction. The signage shall have the following information (as a minimum):

(a) description of development (include an overall concept plan);

- (b) name of developer;
- (c) name of project;
- (d) street address of the site;
- (e) supervising engineer's name and phone number;
- (f) consultant's name and phone number;
- (g) principal contractor's name and phone number; and
- (h) other specialist consultants' names and phone numbers.

(7) Signage and security

All necessary signage and site security shall be provided wholly within the site and in strict accordance with current Workplace Health and Safety (QLD) guidelines and requirements.

(8) Site access

The construction site shall be accessed via one convenient access from a public road. The location and details of this access point is to be approved by council prior to construction commencing. This access point shall be used by all vehicles, equipment and personnel during the approved construction hours of the site. Appropriate vehicle "shake-down" facilities are to be provided at the point of access in accordance with appropriate water quality management objectives for the site. The vehicle shake-down facility is to be a minimum 1.5m long by 3m wide for one-way or 6m wide for two way entrances.

(9) Site fencing

The developer must erect a temporary man-proof fence to restrict unauthorised access into the construction site. The fence is to extend around the entire perimeter of the site with access being provided as outlined above. The developer is to refer to SC6.4.6.29 Boundary fencing for details of the temporary fence.

(10) Site management

The Contractor is responsible for the management of the construction site and control of construction activities throughout the period of works, with particular attention to reducing the impact of the construction work on the public, adjacent and nearby properties and other areas of the site not part of the works. The primary objective is to eliminate the impacts of the temporary and permanent works having regard to:

- (a) work health and safety;
- (b) erosion control;
- (c) acid sulphate soils;
- (d) run-off;
- (e) traffic management;
- (f) disposal of all materials;
- (g) gaseous discharges and odour;
- (h) noise; and
- (i) dust.

Adjacent waterways shall be regularly monitored for turbidity plumes, algal blooms and dead marine life which may be attributable to the construction of the works.

(11) Erosion and sediment control

During the construction phase and up until council accepts the development works or at the end of the defect liability period the contractor shall be responsible for the installation and maintenance of all erosion and sediment control measures on site.

The approved erosion and sediment control plan (ESCP) submitted as part of the operational works or compliance application must be presented during the pre-start meeting. This plan must be presented to council's nominated representative for review and "fit-for-purpose" implementation on the site. If the ESCP requires revision to suit the current conditions of the development site, the plan must be amended to achieve the approved set of water quality outcomes required by council. Upon approval of the ESCP, the procedures and guidelines outlined in the plan for establishing, managing (inspection and monitoring) and maintaining water quality across the development site shall be the responsibility of the contractor.

The Developer/Superintendent must submit to council the as-constructed plans for ESCP, prior to requesting the On-Maintenance inspection.

At the end of the agreed period of implementation and maintenance, all identified temporary sediment control measures must be removed by the developer and the ground reinstated to council's satisfaction.

(12) Suppression of dust

At all times the Contractor shall ensure that dust resulting from the proposed works, including excavation, backfilling, grading and stockpiles is kept to an absolute minimum and to the satisfaction of council, by approved methods.

(13) Noise control

All construction work is to be undertaken pursuant to the *Environmental Protection (Noise) Policy (EPP (Noise))*. Construction works shall be carried out in accordance with the requirements and restrictions relating to hours of work specified in SC6.4.5.2.1(2); and the *Environmental Protection Act 1994*.

(14) Hazardous material

Hazardous materials are to be stored in a hazardous goods store such that it is free from flood and storm tide inundation. The hazardous goods store must ensure that materials cannot enter the environment or cause a public safety nuisance or hazard. Hazardous goods may only be kept on site for the duration of construction and are to be safely removed from site at completion of works, unless otherwise approved by council.

(15) Machinery refuelling

During construction, fuel and petroleum products shall not be stored on the site nor shall construction equipment and machinery be serviced on the site. Procedures shall be developed and implemented by the contractor for the refuelling of machinery and equipment which will minimise any potential for contamination of the site by way of spillage. The procedures shall ensure that refuelling on the site occurs within a designated area that does not drain directly into adjacent stormwater systems or waterways. Any procedures developed and implemented in this regard must include bunding of the refuelling area.

Any spillage of fuels and petroleum products during construction shall be reported to the superintendent. All steps necessary to rectify the contamination shall be undertaken by the contractor prior to the completion of the works and at no cost to council.

(16) Material storage

Materials shall not be stored on site unless approved in writing by the Superintendent or unless material storage details are shown on the drawings and approved by council.

All necessary measures shall be implemented to reduce the potential for environmental damage, which may arise from the storage of materials.

(17) Stockpiling of materials

Wherever possible, materials shall be installed directly in place or continually removed from site, eliminating the need for stockpiles. In all other cases, stockpiling of materials shall be on a temporary basis at the discretion of superintendent.

The location of approved stockpiles shall be in accordance with the ESCP and as a minimum stockpiles shall:

- (a) Remain on site for as little time as practical;
- (b) Be limited to a height of 2m;
- (c) Not to be located within 10m of a residential boundary;
- (d) Have batter slopes, covers and drainage which limit the potential for erosion and/or segregation;
- (e) Be managed in accordance with SC6.4.5.2 Attachment B;
- (f) The contractor is to erect and maintain a temporary sediment fence around all stockpiles for the duration

of the stockpile being on the site.

(18) Vegetation disposal

Burning or burying of waste vegetation on site is not permitted unless otherwise approved by council. Clearing and grubbing of the development site shall otherwise be undertaken in accordance with SC6.4.6.11 Clearing and grubbing.

(19) Work adjacent to trees and protection of environmentally significant vegetation

monitoring and certification will be required.

(a) Protection of trees and vegetation – general

All existing and newly planted trees and vegetation should be noted on the drawings and protected from damage during construction. The approved vegetation protection plan should be available onsite prior to commencement and during works. The vegetation protection plan will identify key stages where

As specified in the vegetation protection plan, a vegetation protection zone must be established on site to ensure the required retention of existing trees and vegetation identified for protection and retention. The vegetation protection zones must be identified as "no-go" areas for construction traffic and meet the following requirements:

- (i) For trees, the extent of the vegetation protection zone is to be determined in accordance with the tree protection zone (TPZ) requirements of AS 4970 *Protection of trees on development sites*.
- (ii) For areas of vegetation not including trees, other areas of natural heritage or hydrologically sensitive features, the extent of the Vegetation Protection Zone is to be determined by a qualified arborist, ecologist, or other approved officer.
- (iii) The Vegetation Protection Zone is to be fenced or barricaded to prevent unauthorised vehicle and machinery access, as per AS4970 *Protection of trees on development sites* and AS4687 *Temporary Fencing and Hoardings*.
- (iv) Signage to indicate "Vegetation Protection Zone No Access" should be installed as per AS4970 Protection of trees on development sites and AS1319 Safety signs for the occupational environment.
- (v) Where required, the tree bark is to be protected by wrapping a triple layer of hessian or rubber matting around the tree trunk.
- (vi) Fixing of temporary service wires, nails, screws, stays, guys and or any other fixing device to trees should be avoided.
- (vii) No fuel, oil dumps or chemicals are allowed to be used or stored within the Vegetation protection zone and the servicing or re-fuelling of equipment and vehicles must be carried out away from the vegetation protection zones.
- (viii) Deposition of wind-blown materials (such as cement) into the protection area should be avoided through the attaching of cloth to the Vegetation Protection Zone fencing.
- (ix) Soil compaction and removal of top soil within the Vegetation Protection Zone is to be avoided. Where compaction occurs, hand methods to de-compact the soil should be used.
- (x) No vehicles are to access or be parked within the Vegetation Protection Zone. Where traffic is unavoidable within the zone, a 300 mm thick layer of mulch over a geotextile fabric should be placed in the area to protect the trees surface roots and to reduce the risk of soil compaction.
- (xi) No storage of material, equipment or temporary building is to take place within the Vegetation Protection Zone, including the placing of spoil from excavation against tree trunks.
- (b) Fill and excavation near trees and vegetation
 - (i) Any underground service installations within the Vegetation protection zone must be bored and the utility authorities must utilise a common trench where possible. Where practical, trenching is to be combined with locations where roots need to be severed for other reasons.
 - (ii) Within the Vegetation protection zone, all excavation must be carried out by hand digging or with the use of "air-excavation" techniques.

- (iii) Where required, trees roots or branches are to be cut cleanly without tearing, with clean, sharp tools (chainsaw, secateurs or hand saw) in accordance with the AS 4373 *Pruning of Amenity Trees* and under the supervision of a qualified arborist with formal qualifications (Level 3 Australian Qualification Framework) or at least 5 years recognised experience in arboriculture.
- (iv) Cutting of tree roots exceeding 50 mm in diameter should be avoided. Where roots must be cut, this should not unduly disturb the remaining root system.
- (v) Any ripped or torn roots are cleanly re-cut as soon as noted.
- (vi) Roots to be left exposed for any period of time are covered with wet hessian and maintained in a moist condition until recovered.
- (vii) Immediately after cutting of any roots, Copper Naphthanate or an equivalent alternative solution is to be applied to the cut surface to prevent the incursion of rot or disease as deemed necessary.
- (viii) Backfill to excavations around tree roots should be with a soil mix similar in consistency and pH value to that of the existing soil.
- (ix) Backfill should be placed in layers of 300 mm loose depth and be compacted to a dry density similar to that of the original surrounding soil using hand methods or light compaction equipment.
- (x) Backfill layers should generally match the soil horizon of the surrounding soil.
- (xi) The depth of fill within the vegetation protection zone should not exceed 200 mm from the original surface level. Immediately after placing any fill around a tree, the area should be watered thoroughly.

(c) Trees to be transplanted

- (i) Trees to be transplanted shall be noted on the drawings and/or shall be marked on site by the superintendent prior to the commencement of construction.
- (ii) Requirements and procedures for transplanting of trees are to be issued by council for each particular species.

(d) Damage to tree or vegetation

- (i) Any unauthorised removal, damage or disturbance undertaken prior to the identification of the protected zone/s (without the required approval) or within the identified protected zone/s shall be rehabilitated by the contractor to the satisfaction of council and at no cost to council.
- (ii) In the event of an unauthorised removal and that rectification works to damaged tree/s or vegetation is impractical, or the rectification work has been carried out by the contractor and is rejected by council, then council may direct the contractor to remove the trees/vegetation as part of the rectification work. The contractor will:
 - (A) replace the damaged tree/vegetation with a tree/vegetation of the same species and similar size to council's satisfaction; or
 - (B) replace the damaged tree/vegetation with a tree/vegetation of a similar size but different species to council's satisfaction; or
 - (C) pay for the cost of replacing the tree/vegetation with the same size and species to council's satisfaction; or
 - (D) replace the damaged tree/vegetation with a smaller tree/vegetation of an approved species and pay for the difference in cost between the new replacement and a specimen of the same size and species, to council's satisfaction.
- (iii) The replacement value of an existing tree/vegetation will be calculated using the Revised Burnley Method under the Draft Australian Standard DR99307 *Amenity Trees Guide to Valuation system.*

(20) Stormwater quality

Development works may cause changes to the quality, quantity and flow rate of stormwater discharged from the site. During the construction phase where soil disturbance and construction activity significantly increases the risk of soil erosion or where the development is required to implement a Stormwater Quality Management Plan (SQMP) that has been approved during the operational works approval phase. Council will then require a detailed maintenance regime to control stormwater quality during the construction phase to be presented during the pre-start meeting for review and acceptance by council unless a detailed maintenance regime has

been presented and accepted by council during the design process.

If the development works involves construction of stormwater quality device/s or is part a catchment with an existing stormwater quality device, then the developer and his contractor must ensure that no stormwater discharge will be permitted to enter such device (directly or indirectly) unless otherwise permitted by council. Refer to SC6.4.6.1 Water sensitive urban design construction and establishment guidelines.

Any temporary stormwater quality device proposed as part of the development works is to be removed and any land or existing infrastructure disturbed or damaged during the installation of any temporary stormwater quality device shall be reinstated to its former condition to the satisfaction and at no cost to council.

(21) Insurance and indemnity

From the commencement of construction until council accepts the development works or the commencement of the maintenance period, the developer or contractor must insure the works against public liability (\$10-\$20 million dollars minimum cover) and other claims arising from the works, and indemnify council against that liability.

Council must be included as an interested party to the insurance policy. The developer must provide council with evidence and a certificate of currency for the insurance and indemnification before commencing the construction works.

(22) Dilapidation survey

Where required by council and where development is directly adjacent to existing infrastructure and improvements, it may be prudent for the developer or his contractor to carry out a dilapidation survey of all the existing adjoining structures prior to construction commencing. This may reduce any damage claims during the construction period. Any damages to adjacent structures as a result of the development works shall be the responsibility of the developer.

(23) Fencing

While undertaking development works, and where appropriate, site fencing is to be erected for the duration of construction activities. Fencing is required to restrict unauthorised site access and to ensure the safety of persons from the subject site and any works on the adjoining road reserve and/or premises.

If existing fencing is to be altered or if there is no existing site fencing, temporary fencing, as a minimum, shall be provided and maintained for the duration of the construction to prevent unauthorised entry into the property or work area from any adjoining road reserve or property. The reinstatement of fencing and removal of temporary fencing on completion of the work shall be undertaken.

A construction site may provide any additional amount of security and/or fencing that is considered necessary that will improve the safety of the public or persons working on the site.

(24) Environment

All work shall be carried out in such a manner as to avoid nuisance and/or Environmental Harm. Development shall be planned and executed so that the works undertaken avoid contamination of the site and its surroundings by taking all reasonable and practical measures to prevent or minimise harm (general environmental duty).

Herbicides and other toxic chemicals shall not be used on the site without the prior written approval of the council or other relevant authority.

(25) Lighting

All lighting associated with the construction activity shall be installed and used so that lighting does not adversely affect the adjoining amenity of nearby sensitive uses, sensitive environmental areas or pose a safety hazard on adjacent road networks. All public road/street lighting systems must be designed in accordance with AS 1158 and must be approved by Ergon prior to construction.

Blasting will generally not be permitted. If blasting is necessary and there are no alternatives, it shall be carried out strictly in accordance with SC6.4.6.10 Earthworks (construction) and any other relevant construction specifications found in SC6.4.6 of the Development manual.

(27) Vibration

Ground vibration levels, transmitted from the construction works, rock breaking, drilling, and piling, operating items of plant or other noisy activities shall not exceed levels that are close to the lower level of human perception nor is it to cause any unacceptable damage to any adjoining buildings or infrastructure. Acceptable practices and vibration thresholds shall be determined in accordance with current Statutory Regulations.

Acceptable practices and vibration thresholds shall be determined in accordance with current Statutory Regulations.

A complaints management system should be devised which includes corrective and preventative actions. Consultation with and information supplied to nearby residents, workers and any other sensitive noise receptors is to be undertaken when vibration is known to be generated and is considered sufficient to warrant notification.

Editor's note—the results and recommendations of reporting on noise and vibration, as detailed in SC6.4.3.15 Noise and vibration assessment guidelines, associated with a particular development will be required to be implemented.

Editor's note—the Contractor shall be responsible for any damage and compensation payments as a result of vibration.

The control of ground vibration as a result of blasting shall be strictly in accordance with SC6.4.6.10 Earthworks (construction) and any other relevant construction specifications found in SC6.4.6 of the Development manual and will be solely at the risk and responsibility of the developer.

SC6.4.5.3 Quality management system

- (1) Townsville City Council requires an emphasis on quality for the development works being delivered by developers. Where a condition for the approval of the development works requires the works to be completed as a "Quality Controlled and Assured Development", the developer must engage consultants and contractors with the necessary level of Quality Assurance accreditation to undertake and certify the development works.
- (2) Quality management system It is a requirement for a "Quality Controlled and Assured Development Contract" that the contractor shall plan, develop and maintain a documented Quality System in accordance with this section and the current requirements of AS/NZS ISO 9001.
 - (a) Quality manual
 - This is a document setting out the general quality policies, procedures and practices of an organisation. The development of this document shall cover and include the requirements as specified in the Quality System Documentation section of AS/NZS 3905.12 with guidance to preparation by AS/NZS ISO 10013. Additionally, it must include standard method statements and inspection and test plans for the activities undertaken by the Contractor. The following details shall be provided by appropriate annexures to the Company Quality Manual:
 - (i) Organisational Structure this provides information regarding the management structure of the project with details of the specific responsibilities and authorities of the nominated personnel, which includes but is not limited to:
 - (A) a project quality management representative is appointed by the Contractor for a specific project with the authority and responsibility for the implementation and operation of the quality plan, to ensure that Quality System requirements are not subordinated to design and productivity. Details of this person's qualifications, technical experience and present position are also to be provided;
 - (B) the contracted testing organisation details of the personnel who will be conducting each type of compliance inspection of testing; and
 - (C) the person authorised to change construction processes on site; and
 - (ii) Register of Method Statements the register shall list all Method Statements that are to be included in the project quality plan for the development contract and shall include any suitable method statements already incorporated in the Company Quality Manual.
 - (b) Project quality plan
 - The Quality System as expressed in the project quality plan shall be used throughout the course of the construction to ensure that the quality of the Contractor's and any sub contractor's work complies with all the requirements under this section. The Company Quality Manual, method statements and checklists and other project specific components shall make up the Project Quality Plan. The project quality plan must generally conform to the recommendations of AS/NZS ISO 10006. A concept illustration is shown in Figure SC6.4.5.3.1 Project quality management system documentation.




Figure SC6.4.5.3.1 Project quality management system documentation

- (3) Where a "Quality Controlled and Assured Development" is not a requirement, a quality plan is not therefore required to be provided but it will be necessary as a minimum requirement that:
 - (a) the nominated Superintendent or Consultant are suitably and appropriately qualified and experienced;
 - (b) a work quality plan must be submitted to council for review and acceptance prior the pre-start meeting or commencement of works. The work plan must outline a program of inspection and testing regime that will ensure an adequate control of the progress and correctness of the work in accordance with the accepted design plans and specification;
 - (c) upon completion of the development works and prior to council accepting the completed development works, all records as required on the work quality plan must be submitted to council to demonstrate compliance with the accepted work quality plan; and
 - (d) the full cost of all required testing as per the work plan shall be the responsibility of the developer or the contractor. These tests are required to ensure that the materials and the works that were carried out conform to the accepted design specification and standard.
- (4) Quality management system procedures
 - (a) Quality control system
 - (i) Lots

All items of work shall be subdivided into lots. Each lot shall be given a unique lot number and shall be chosen by the Contractor but must be within the limits given in SC6.4.5.3 Attachment A Maximum lot sizes and minimum test frequencies. In general, the size of the lot shall not exceed one day's output for each work process designated for lot testing.

The lot numbers shall be used as identifiers on all surveys and test results. The Contractor shall determine the bounds of each lot before sampling and shall identify each lot clearly. The

boundaries of a lot may be changed if subsequent events cause the original lot to be no longer essentially homogeneous.

The lot identification system and sample numbering system shall allow test results to be positively identified with material incorporated in the works.

(ii) Sampling and testing

All compliance inspections and tests shall be based on lots. The maximum lot sizes and minimum testing frequencies are listed in the Attachments to the relevant sub-sections and/or in SC6.4.5.3 Attachment A Maximum lot sizes and minimum test frequencies.

Where no minimum frequency of testing, or maximum lot size is stated in the sub-section, the Contractor shall nominate appropriate frequencies for the Superintendent's approval. Sampling shall not be restricted to locations dimensioned or otherwise defined for setting out the works in the drawings or sub-section, but shall be undertaken in a random or unbiased manner, as approved by the Superintendent, at any location within the works to demonstrate its compliance with the sub-section.

Where test methods are nominated in the sub-section, sampling and testing shall be carried out by a (NATA) National Association of Testing Authorities registered laboratory accredited for those test methods and sampling procedures. Sampling shall be conducted by personnel from the NATA registered laboratory which has been accredited for that sampling procedure and shall be supervised by the approved signatory from that laboratory. Test results shall be reported on NATA endorsed test documentation which shall include a statement by the approved signatory certifying that the correct sampling procedures have been followed.

Random sampling techniques shall be used for each lot for the control of compaction of each continuous layer of earthworks, flexible pavement and asphalt. SC6.4.5.3 Attachment B Random sampling defines the method to be used for determining test locations of random sampling in each lot. For quality control of processes other than compaction of layers of earthworks, flexible pavement and asphalt, the sampling locations will be proposed by the Contractor and will require the approval of the Superintendent. All samples shall be each considered to be representative of the lot and all test results will be required to meet the appropriate tolerances for the lot.

The latest NATA advice of the terms of registration and current signatories for the laboratories are to be included within the quality plan shall which will be providing the compliance test reports.

The NATA registered laboratory must provide inspection, testing and measuring equipment capable of producing the precision and/or degree of accuracy specified in the referenced test methods and this shall be made available by providing evidence or records of calibration.

(iii) Surveying

The Contractor shall engage qualified surveyors who are eligible for membership of the Institution of Surveyors, Australia or the Institution of Engineering and Mining Surveyors, Australia to supervise and take responsibility for all Surveying Control.

- (iv) Surveying Control shall include all measurement, calculation and record procedures necessary to:
 - (A) set out the works;
 - (B) verify conformance to the drawings and sub-section in relation to dimensions, tolerances and three dimensional position; and
 - (C) determine lengths, areas or volumes of materials or products, where required for measurement of work.

The procedures and equipment used must be capable of attaining the tolerances required in the relevant construction specification. Sampling for conformance verification purposes shall not be restricted to the locations used to set out the Works.

The Contractor shall submit a survey conformance report to the Superintendent for each lot or

component where design levels, position and/or tolerances have been specified. The report shall show "specified vs. actual" for position (defined by co-ordinates or chainage and offset), level and tolerance as appropriate and shall be certified by the qualified surveyor responsible for the verification survey.

(v) Records and quality control documentation Conformance records shall be stored and maintained such that they are readily retrievable and in facilities that provide a suitable environment to minimise deterioration or damage and to prevent loss.

The Contractor shall submit all conformance records to the Superintendent for inspection and approval. If requested by the Superintendent, the Contractor shall provide copies of the records or test results at no cost to the Developer.

The Contractor shall maintain a quality register which contains all quality control records such as test results, completed check lists, certificates of compliance, and consignment dockets for materials procured.

Prior to achieving practical completion or the commencement of the defects liability period or prior to acceptance of work as "Finally Complete", the Contractor shall provide council through the Superintendent a copy of the quality register and other required quality control documents as required in this section.

- (5) Quality assurance system is the management of actions covering planning, quality control testing, inspection and verification procedures integrated with production to provide a product fit for the purpose.
 - (a) Inspection and test plan (ITP) is the document which identifies the specific inspections and tests required to be carried out for on development works including hold points. The ITP is to be prepared by an appropriately experienced consultant identifying specific inspections and tests to be carried out for each item of development works. Refer to council's minimum ITP requirement on SC6.4.5.3 Attachment D Minimum inspection and test plan.

As a minimum, the inspection and test plans must contain the following information:

- lot references;
- activity description;
- specification requirements (if not provided, referenced specification);
- sampling methodology;
- test frequency and method; and
- identify responsibilities for inspection and testing and approval.

The superintendent shall audit the contractor's work on a regular basis and provide sufficient site presence and in particular at inspection points identified in the Inspection and testing plan as set out in the construction schedules and agreed to and accepted by council. Inspections by council shall not in any way diminish the responsibility of the consultant and the superintendent to adequately audit the works. Auditing shall include regular site inspections which will be conducted with the presence of the contractor's representative to confirm acceptability of works as complying with the design intent and other council requirements.

Inspection and test plans will typically have an associated check list which shall require completion for each particular lot. Prior to council's acceptance of completed development works all documentation relating to compliance to the agreed and accepted ITP are to be submitted by the Contractor and/or the Superintendent which will form part of the Consultants' certification that the works have been carried out and inspected in accordance with the agreed and accepted ITP.

(A) Inspections

The contractor shall ensure that any particular stage of work to be inspected has been satisfactorily completed before requesting an inspection by the superintendent and/or council. A minimum of 24 hours' notice (except for off maintenance inspection which requires a minimum of 7 days) is required to enable arrangements to be made for an

inspection. Responses to the requests within the prescribed minimums are not guaranteed, although every effort will be made by council to accommodate request where possible. All council required inspections must be carried out Monday to Friday unless other arrangements have been agreed.

Incoming inspections shall be required for deliveries of materials that will be subsequently included in one or more lots. When completing check lists for particular lots the inspection status shall be cited.

In-process and compliance inspections shall be completed by a responsible officer nominated in the check list and certified by the Contractor's Quality Management Register (QMR) indicating that the work has been completed in accordance with the contract documents.

The Contractor shall establish and maintain a system to ensure and demonstrate that all products or parts of products requiring inspection and/or testing are so inspected and/or tested. The Contractor shall also establish and maintain a system for identifying the inspection status for all lots of work.

(B) Hold points and witness points

To assure compliance with the specified standards and requirements, mandatory hold points shall apply. Hold points are those stages during the construction/manufacturing process where the technical specifications require "approval by the Superintendent" or where a non-conformance report (NCR) or notice of non-conformance (NNC) has been issued. The Contractor shall not proceed past the hold point until approval has been received from the Superintendent to proceed. For ease of identification hold points may also be annotated on the margins of technical specifications.

To obtain the approval to proceed from the Superintendent, the Contractor shall:

- provide the information required by the technical specifications;
- ensure and certify that the particular lot/process is conforming;
- ensure and certify that all underlying and adjacent lots affected by the lot in question are conforming; and
- submit the appropriate form (check list, NCR or NNC) at least 24 hours prior to the time the Contractor wishes to proceed with the placement/construction of the next lot, unless some alternative arrangements have been agreed with the Superintendent.

If the hold point has resulted from a NCR or NNC, the Superintendent's approval may be conditional on a witness point being included.

(b) Quality assurance activities

(A) Document control

In addition to the requirements of AS/NZS ISO 9001 and AS/NZS 3905.2, the quality plan shall specify the method of keeping quality registers, tracking and handling of NCRs, NCC, NNCs and other site correspondence.

(B) Method statements

A document that specifies the key steps and sequence in the manufacture/construction for an activity; what, how and by whom it shall be done; what materials and equipment shall be used to achieve the required quality standards.

Method statements shall be provided for all activities scheduled in SC6.4.5.3 Attachment C Method statement requirements. This requirement applies to both contract and subcontracted work. The documentation shall cover, as applicable, planning, methods, verification and control.

The presentation of method statements may be either descriptive, in the form of flow charts or a combination of both. In either case it must be accompanied by a check list which shall include the

relevant inspection and test points, surveying control points and Hold Points and the officer responsible to verify each check point.

A system audit of each method statement shall be carried out by the Contractor whilst the process is in effect. In the absence of a method statement for activities where it has been specified, this will automatically create a hold point.

(C) Identification of lots and traceability

All items of work shall be subdivided into lots. Lots shall be chosen by the Contractor but shall be within the limits given in SC6.4.5.3 Attachment A. lot numbers are to be used as identifiers on all quality system data. Each lot shall be given a unique lot number. The allocation of lot numbers shall be carried out by the Contractor specific to each item of work and provides a lot numbering system which conforms to these requirements:

The Quality Register must contain records of lot number which provides information such as:

- location of the lot (e.g. start and end chainage, layer and lateral location or a particular structure);
- note regarding conformance/non-conformance (e.g. NCR, CPAR Registers); and
- table of test results (summary) and their respective locations and numerical identification.

In cases where non-conforming lots are identified, a new identification number shall be allocated to the resubmitted documentation, but reference to the original lot number must be included.

The Contractor is responsible in determining the bounds of each lot before sampling and shall physically identify each lot clearly. The physical identification of a lot shall be maintained until the Contractor has ensured that the lot has achieved the specified quality.

To ensure all site personnel can readily identify where the particular lots are in the field, the Contractor shall implement a field identification system which will clearly identify the bounds of each lot and the lot number. This identification system shall be detailed in the quality plan and shall be maintained during all stages of construction of the lot.

The boundaries of a lot may be changed if subsequent events cause the original lot to be no longer essentially homogeneous. This will require appropriate notation in the Quality Register by the QMR.

The lot identification system, site records and sample numbering system shall allow test results to be positively identified with material incorporated in the works. Traceability is required for concrete loads, asphalt loads and steel plate as follows:

- concrete used in bridge components, cast-in-place box culverts, retaining walls, road
 pavement sub base and base. Asphalt used in wearing courses, intermediate courses and
 drainage layers;
- the trace shall start at the batch plant and finish at the location where the concrete or asphalt is incorporated in the Works. Records shall be kept of the batch quantities, mix and despatch time, testing details and location of placement; and
- steel plate in bridge girders and bridge columns. The trace shall start at the steelworks and
 finish at the location of the plate in the girder or column. Records shall be kept of the steel
 heat number, testing details and location of the plate in the girder or column.

(D) Surveying control

Surveying control shall be treated as a separate system element and shall include all measurement, calculation and record procedures necessary to:

- set out the Works;
- verify conformance to the drawings and specification in relation to dimensions, tolerances and three dimensional position; and
- determine lengths, areas or volumes of materials or products, where required for

measurement of work.

The method statements for surveying control shall address the process control parameters in AS/NZS 3905.2 for special processes which cannot be fully verified by subsequent inspection and test.

The Contractor shall appoint qualified surveyors who are eligible for membership of the Institution of Surveyors, Australia or the Institution of Engineering and Mining Surveyors, Australia to supervise and take responsibility for all surveying control.

The procedures and equipment used must be capable of attaining the tolerances nominated in the specification. Sampling for conformance verification purposes shall not be restricted to the locations used to set out the Works.

The Contractor shall submit a survey conformance report for each lot or component where design levels, position and/or tolerances have been specified.

The survey conformance report shall show "specified vs. actual" for position (defined by coordinates or chainage and offset), level and tolerance as appropriate and shall be certified by the qualified surveyor responsible for the verification survey.

Where work is to be covered up after conformance has been achieved, a hold point shall apply until the survey conformance report has been submitted.

All survey records shall be included in the quality records and recorded in the quality register. Verification field book pages shall be clearly labelled, dated and signed by the surveyor with cross indexed references to equipment used lot/component identification and associated survey conformance reports. Where automatic data recording systems are used for verification surveys, a printout of both raw (field) data and reduced data shall be retained in a similar manner as conventional field books.

(E) Sampling and testing

The inspection and test plans shall include details of the sampling methods. Sampling shall not be restricted to locations dimensioned or otherwise defined for setting out the works in the drawings or specification, but shall be undertaken in a random or unbiased manner, as approved by the Superintendent, at any location within the works to demonstrate its compliance with the specification.

The maximum lot sizes and minimum testing frequencies are listed in the attachments to the relevant sub-sections and/or in SC6.4.5.3 Attachment A to this sub-section. Where no minimum frequency of testing, or maximum lot size is stated in the specification, the inspection and test plan(s) shall nominate appropriate frequencies for the Superintendent's approval.

The inspection and test plans shall also uphold any time limits for testing which may be imposed by the specifications. The responsibility for completion of inspections, tests and documentation shall be stated in the quality plan.

Statistical techniques - random sampling techniques shall be used for each lot for the control of compaction of each continuous layer of earthworks, flexible pavement and asphalt. SC6.4.5.3 Attachment B defines the method to be used for determining test locations of random sampling in each lot. SC6.4.5.3 Attachment A lists the maximum lot sizes and minimum test frequencies for the specified activities.

For compaction control of processes other than layers of earthworks, flexible pavement and asphalt, the sampling procedure will be proposed by the Contractor in his method statement and will require the approval of the Superintendent. In such cases the samples shall be each considered to be representative and all test results will be required to meet the appropriate

tolerances for the lot.

Every testing agency or person providing written test reports for any and all testing undertaken shall use unique consecutive project specific serial numbering of the reports for identification and auditing purposes.

The Contractor shall reinstate all core holes, test holes, excavations and any other disturbance resulting from any testing activity. The reinstatement shall be to a standard which is at least equal to the specified requirements for the particular work.

(F) Records and quality assurance documentation

The Contractor shall keep and maintain all Quality System records in a Quality Register as required by AS/NZS ISO 9001, AS/NZS 3905.2 and this sub-section. They shall be systematically recorded, indexed and filed so as to be retrievable and accessible to the Superintendent or an appointed Quality Auditor on a job basis within 1 working day of requisition.

Conformance records shall be stored and maintained such that they are readily retrievable and in facilities that provide a suitable environment to minimise deterioration or damage and to prevent loss.

The Contractor shall make the quality records available to the Superintendent at all reasonable times. If requested by the Superintendent, the Contractor shall provide copies of the records or test results at no cost to the developer.

Prior to achieving practical completion or the commencement of the defects liability period or prior to acceptance of work as "Finally Complete", the Contractor shall provide council, through the Superintendent, a copy of the quality register and other required quality assurance documents as required in this section.

(G) Non-conformance

In circumstances where there is a concern about workmanship, construction methodology or materials (e.g. variation to the approved work specification), council's representative and/or Superintendent may require the Consultant and/ or contractor respectively to provide a non-conformance certificate (NCC) (template provided at SC6.4.5.3 Attachment E Non-conformance certificate template). The NCC will be required to be endorsed by the relevant design Consultant. A non-conformance report (NCR) (template provided at SC6.4.5.3 Attachment F Non-conformance report template) is required to be issued by the Contractor addressing intended variations to approved specifications, work method statements or standards by providing proposed disposition.

In the event that the above has not been satisfied and to ensure compliance with the required standards, Superintendent and/or council may issue a Notice of Non-Conformance (NNC) (template provided at SC6.4.5.3 Attachment G Notice of non-conformance template) to the Contractor. The NNC shall be issued within 1 working day of the non-conformance being identified during an inspection or during scheduled audit inspections, i.e. hold points and witness points. Upon issuance of the NNC, the Contractor must not continue the particular work in question unless an appropriate disposition (to be provided within five working days from issuance of the corrective and preventive action request (CPAR)) has been provided and agreed in accordance with the CPAR (template provided on SC6.4.5.3 Attachment H Corrective and preventative action request template). This is to be undertaken by the Contractor if the NNC identifies non-conforming work which has been provided by the relevant design or construction consultant (Superintendent). Similarly, for council initiated NNC, work shall commence upon council's acceptance of the proposed disposition in accordance with the CPAR. To avoid recurrence of non-conformance issues, all CPARs shall require joint sign off by the Contractor and Superintendent, and council for a council issued NNC. This procedure will require the Contractor to record the CPAR on the relevant issued NNC. Under no circumstances will the deliberation on the disposition of a nonconformance issue be used to justify delays to the construction schedule/period.

The Contractor shall advise the Superintendent in the NCR of the proposed disposition of the particular non-conformance. This proposed disposition will constitute corrective action for the lot or lots referred to in the NCR and may comprise one of the following:

- propose additional works to bring the lot up to the specified standard; or
- replace all or part of the lot to bring it up to the specified standard; or
- request utilisation of a lot for a reduced level of service if such a clause exists in the relevant technical specification; or
- for incidental defects, request that the Superintendent accept the lot without alteration as an exception with or without alteration to the respective unit rates.

Any proposed disposition shall be subject to the approval of the Superintendent. Reworked/replaced lots shall be verified to conform to the specified requirements.

The contractor shall establish a suitable numbering and registration system for all NCRs and NNCs. All non-conformance reports and relevant documentation are required to be submitted to council prior acceptance of development works, to ensure that all departure from the originally accepted requirement and appropriate disposition has been done in accordance with the agreed CPAR.

A process flow diagram of the above processes is shown on Figure SC6.4.5.3.2.




Figure SC6.4.5.3.2 Non-conformance flow diagram

(H) Inspection fees

A works inspection fee (at the rate applicable at the time of payment) must be paid prior to the development works being accepted by council at on maintenance or final completion.

SC6.4.5.3 Attachment A Maximum lot sizes and minimum test frequencies General

Where material/product quality certification can be obtained from the supplier, tests listed per contract/separable part need not be repeated and where no Queensland Department of Transport and Main Roads (DTMR) Test Methods are available, Australian Standards or NSW Roads and Traffic Authority (RTA) Test Methods are specified.

Table SC6.4.5.3.1 Earthworks (SC6.4.6.10)

Activity	Key Quality Verification	Maximum Lot	Minimum Test	Test Method	
a ::	Requirements	Size	Frequency		
Stripping Topsoil	Surface Levels	10,000m ²	1 Cross Section per 25m	Survey	
Excavation	Geometry	10,000m ²	1 Cross Section per 25m	Survey	
Floor of Cuttings	Material Quality—CBR	5,000m ²	1 per	AS1289.6.1.1	
			1,000m ^{2*} or Material Type	DTMR Materials Testing Manual	
	Compaction	10,000m²	1 per 500m ²	AS1289.5.4.1	
Deflection Control	Benkelman Beam Deflection or	Per days	4 per 1000 m ² or	DTMR Materials	
	Equivalent	production	minimum 10 per lot	Testing Manual	
	No visible vertical movement under proof roll	One layer 5,000m2 or max 1 day's placement	Whole area	Visual	
Foundation for	Compaction	5,000m²	1 per 500m ²	AS1289.5.4.1	
Embankments					
Embankments					
General	Geometry	One layer 10,000m ²	1 Cross Section per 25m	Survey	
	Material Quality - CBR	One layer 5,000m²	1 per 800m³ or Material Type	AS1289.6.1.1	
Road Carriageway	Compaction/Moisture Content	One layer 5,000m ²	1 per 250m ³	AS1289.5.1.1 AS1289.5.4.1 AS1289.5.7.1	
Embankments					
Select Zone	Geometry	One layer 10,000m ²	1 Cross Section per 25m	Survey	
	Material Quality				
	Maximum Particle SizeCBR	10,000m² 10,000m²	1 per 1,000m ^{3*} 1 per 500m ^{3*} or Material Type	AS1289.6.1.1	
	Compaction/Moisture Content	One layer 5,000m ²	1 per 500m²	AS1289.5.1.1, AS1289.5.4.1 AS1289.5.7.1	

	Material Quality			
Bridges, Retaining Walls				
and Cast-in-Situ Culverts				
	Maximum Particle Size	1 Structure	1 per 200m ³	AS1289.3.3.1
				AS1141.11
	Plasticity Index	1 Structure	1 per 200m ³	AS1289.3.3.1
	Compaction/Moisture Content	1 Structure	2 per lot	AS1289.5.1.1,
				AS1289.5.4.1
				AS1289.5.7.1

^{*} Note—or part thereof, per lot.

Table SC6.4.5.3.2 Stormwater drainage (SC6.4.6.4), Drainage structures (SC6.4.6.5), Pipe drainage (SC6.4.6.6), Precast box culverts (SC6.4.6.7) and Open drains (SC6.4.6.9)

Activity	Key Quality Verification Requirements	Maximum Lot Size	Minimum Test Frequency	Test Method
Supply of Precast	Precast Quality—	1 batch	1 per	
Units	Suppliers documentary evidence and		type/size/class	
	certification		per batch	
Siting and Excavation	Geometry	1 drainage	1 per drainage	Survey
		line/structure	line/structure	
Foundation	Compaction	1 drainage	1 per 40 lin m*	AS1289.5.4.1,
		line/structure		AS1289.5.7.1
				Visual
Material surrounding	Material Quality	1 drainage	1 per material	AS1289.4.3.1
Steel Structures	pH/Electrical Resistivity	line/structure		AS1289.4.4.1
Bedding	Material Quality			
(Bed, haunch, sides and overlay for HS type support)	Particle Size Distribution	1 contract	1 per 200m ^{3*}	AS1141.11
	Compaction/Moisture Content	1 drainage	1 per layer, per	AS1289.5.7.1,
		line/structure	40 lin m	AS1289.5.4.1
Concrete Bedding or	Geometry		1 Cross Section	Survey and 3m
Lining			per 25m	Straight Edge
Installation of Precast	Geometry	1 drainage	1 per drainage	Survey
Units		line/structure	line/structure	
Selected Backfill	Material Quality			
(Backfill, sides and overlay for non HS type support)	Maximum Particle Size	1 contract	1 per 500m ^{3*}	
	Plasticity Index	1 contract	1 per 500m ^{3*}	AS1289.3.3.1
	Compaction/Moisture Content	1 drainage	2 per lot	AS1289.5.7.1,
		line/structure		AS1289.5.4.1
Rock Fill for Gabions/ Wire Mattresses	Material Quality:			
	Wet Strength	1 contract	1 per contract	AS1141.22
	Wet/Dry Strength Variation	1 contract	1 per contract	AS1141.22
Kerb and Gutter	Geometry	1,000 lin m	1 Cross Section	Survey and 3m
			per 25m and	Straight Edge
			change of	
			direction	

^{*} Note—or part thereof, per lot.

Table SC6.4.5.3.3 Subsoil, foundation and pavement drains (SC6.4.6.20), Subsurface drainage (SC6.4.6.21), Drainage mats (SC6.4.6.8)

Activity	Key Quality Verification	Maximum	Minimum	Test
	Requirements	Lot Size	Test Frequency	Method
Material Supply	Material Quality—Supplier's documentary evidence and certification of:			
	Pipe	1 contract/size	1 per type/size	
	Filter Material			
	Grading (Type A, B, C, D)	1 contract/size	1 pertype	AS1141.11
	Coefficient of Permeability (Type B)	1 contract/size	1 per type	AS1289.5.5.1 ASTM-D2434-68
	Grading Variation after Treatment (Type B)	1 contract/size	1 pertype	AS1141.11
	Wet Strength (Type C, D)	1 contract/size	1 pertype	AS1141.22
	10% Fines Wet/Dry (Type C, D)	1 contract/size	1 pertype	AS1141.22
	Appearance (Type D)	1 contract	1 pertype	Table B1 Appendix B of AS2758.1
	Geotextile - Supplier's documentary evidence	1 contract	1 pertype	AS3706 (Test) AS3705
Excavation - Trench Base	Line and Grade	1 drainage line	1 per drainage line	Survey
Bedding and Backfill				
Filter Material	Geometry	1 drainage line	Visual	Survey
	Compaction	1 drainage line	1 per line	AS1289.5.6.1
Selected Backfill	Geometry	1 drainage line	Visual	Survey
	Compaction	1 drainage line	1 per line	AS1289.4.1
Earth Backfill	Geometry	1 drainage line	Visual	Survey
Drainage Mat	Geometry	2000m²	1 Cross Section per 25m	Survey

Table SC6.4.5.3.4 Stabilisation (SC6.4.6.19)

Activity	Key quality verification requirements	Maximum lot size	Minimum test frequency	Test method
Material Supply	Material Quality - Supplier's documentary evidence and certification of (as per MRTS07A, MRTS07B, MRTS07C and MRTS08):			
	• Cement	1 contract	Туре	AS3972
	 Quicklime 			
	Available Lime (CaO content)	1 contract	Туре	AS3588.12
	Slaking Rate	1 contract	1 per contract	T432
	Particle Size Dist'n	1 contract	1 per contract	AS1141.11
	Hydrated Lime			
	Available Lime (CaOH2)	1 contract	1 per contract	AS3583.12
	Residue on Sieving	1 contract	1 per contract	AS3583.14
	Ground Blast Furnace Slag	1 contract	1 per contract	AS3583.2
	• Flyash	1 contract	1 per contract	AS3583.1
	Blended Stabilising Agent	1 contract	1 per contract	
	• Water			
	Chloride ion content	1 contract	1 per contract	AS3583.13
	Sulphate ion content	1 contract	1 per contract	AS1289.4.2.1
	Undissolved solids	1 contract	1 per contract	
Mix Design	NATA certification - Supplier's documentary evidence and certification	1 mix	1 per mix	
Stationary Mixing Plant	Application rate of stabilising agent	1 day's production	1 per 100t	
	Unconfined Compressive strength of product	1 day's production	1 per 400t	AS5101.4
In-Situ Spreading	Spread rate	1 layer 1,000m ²	1 per lot or 1 per 500m ²	DTMR Materials Testing Manual
	Mix uniformity	1 layer 1,000m²	1 per 500m ²	Visual
	Unconfined Compressive Strength of product	1 day's production	1 per 100t	AS5101.4

Trimming and Compaction	Geometry	1 layer 3,000m ² ,	One cross section	Survey
		or 1day's	per 25m	
		placement		
	Surface Quality	"	10 per	3m Straight
			200m lane	Edge
			length*	
	Average Layer thickness	"	1 per lot	
	Average Width	"	1 per lot	Measure/Survey
	Compaction	1 layer	1 per lot	As specified in
		5000m ² or		SC6.4.6.19(5)
		min. of 3 if		
		less than		
		5000m ²		

Note— or part thereof, per lot.

Table SC6.4.5.3.5 Flexible pavements (SC6.4.6.12)

Activity	Key Quality Verification	Maximum Lot Size	Minimum Test	Test Method
D (M ())	Requirements		Frequency	Method
Pavement Materials	Material Quality - Supplier's	1 contract		
Supply	documentary evidence and certification			
	to meet MRTS05, MRTS07B and MRTS08 requirements - Type 2.1 for			
	base, Type 2.3 for subbase and Type			
	2.4 for lower subbase.			
	Particle Size Distribution		1 per 1,000t	Q103A, AS1289.3.6.1
	Fine and Particle Size Distribution			AS 1209.3.0.1
	Ratio			
	Liquid Limit		1 per 1,000t	Q104A, Q104D
	Plastic Limit		1 per 1,000t	Q105, AS1289.3.2.1
	Plasticity Index		1 per 1,000t	Q105, AS1289.3.2.1
	California Bearing Ration (soaked)		1 per 5,000t	Q113A
	Particle Shape		1 per 1,000t	Q201,
	Ten Percent Fines Value (Wet)		1 per 5,000t	AS1141.15 Q205B,
				AS1141.22
	Wet/Dry Strength Variation		1 per 5,000t	Q205C,
				AS1141.22
	Degradation Factor (Source Rock)		1 per contract	Q208A,
	Unconfined Community Community		4 5 0001	AS1141.25.1
	 Unconfined Compressive Strength (Standard Compaction) 		1 per 5,000t	TCC-001, Q115 AS5101.4

	 Unconfined Compressive Strength (Bound/Modified) 	1 contract	1 per mix design	Q115, AS5101.4
	Lime modified/Modified pavement materials	1 contract	1	As specified in SC6.4.5.3.4 Stabilisation
Compaction	Geometry: Alignment and Level	One layer	1 Cross Section	Survey
Assessment		2,000m ² or	per 15m	
	Width and Surface Trim	max 1 day's placement		Measure and 3m Straight Edge
	Compaction/Moisture Content/	One layer 5,000m ² or		AS1289.5.1.1, Q142A,
	Dry Density Testing	max 1 day's placement	3 per lot if less	AS1289.5.4.1 AS1289.5.8.1
Deflection Control	Benkelman Beam Deflection or	Per days	4 per 1000 m² or	Q701
	Equivalent	production	minimum 10 per	
			lot	Visual
	No visible vertical movement under proof	One layer		
	roll		Whole area	
		5,000m ² or max		
		1 day's		
		placement		

^{*} **Note**—or part thereof, per lot.

Table SC6.4.5.3.6 Sprayed bituminous surfacing (SC6.4.6.17)

Activity	Key Quality Verification	Maximum	Minimum	Test
	Requirements	Lot Size	Test Frequency	Method
Materials Supply	Material Quality - Suppliers			
	documentary evidence and certification			
	of:			
	Class 170 Bitumen	1 contract	1 per contract	MRTS.17
	Refinery Cutback Bitumen	1 contract	1 per contract	MRTS.17
	Polymer Modified Binder	1 contract	1 per contract	MRTS.18
	Polymer Modified Billider	Contract	per contract	IVIIX 13.16
	Bitumen Adhesion Agent	1 contract	1 per contract	
	Ĭ		'	
	Cutback Oils	1 contract	1 per contract	
	Aggregate Precoating Agent	1 contract	1 per contract	
	Aggregate	1 contract	1 per contract	MRTS.22
Application Rates	Binder	1 day's operation	Calculate per	As per spray
, ipplication rates	511401	1	spray run	sheet
	Aggregate	1 day's operation	1''	As per spray
			spray run	sheet

Note— one per contract or change in material.

Table SC6.4.5.3.7 Asphaltic concrete (SC6.4.6.13)

Activity	Key Quality Verification Requirements	Maximum Lot Size	Minimum Test Frequency	Test Method
Materials Supply	Material Quality - Supplier's	OIZC	requeries	
atoaio Gappi,	documentary evidence and certification			
	of:			
	Coarse and Fine Aggregates			MRTS 30
	Grading	1 wk's prod'n	1 per contract or	MRTS 30
			material change	
	- Moisture Content	1 wk's prod'n	1 per contract or	MRTS 30
	- Moisture Content	I WKS PIOUTI	material change	WINTS 50
			material enange	
	- Wet Strength	1 contract	1 per contract or	MRTS 30
			material change	
	- Wet/Dry Strength Variation	1 contract	1 per contract or	MRTS 30
			material change	
	- Particle Shape	1 contract	1 per contract or	MDTC 20
	- Faiticle Shape	Contract	material change	IVIK 13 30
			material enange	
	- Fractured Faces	1 contract	1 per contract or	MRTS 30
			material change	
	Polishing Agg Friction Value	1 contract	1 per contract or	MRTS 30
			material change	
	- Mineral Filler	1 contract or	1 per contract or	MRTS 30
	Willera Filler	1 month's	material change	WITCH 0 00
		production		
	- Bitumen Binder	1 refinery	1 per contract or	MRTS 17
		batching	material change	
	Polymer Modified Bitumen			MRTS 18
	■ Elasticity Recovery at 60°C	1 production	1 per contract or	MRTS 30
	Liability Nocevery at 66 6	batch by supplier	l '	WII (1 0 00
		,,,,,,		
	Viscosity on ER at 60⁰C			MRTS 30
	Torsional Recovery at 25°C			MRTS 30
	Vigopoity at 18000			
	 Viscosity at 180°C Bitumen Adhesion Agent 	1 contract	1 per contract or	MRTS 30
	Ditalifoli Adilesion Agent	Contract	material change	IVIIX I O OU
	Resistance to Stripping			
	Reclaimed Asphalt Pavement	1 stockpile	1 per contract or	MRTS 30
	(RAP)		material change	
		1		

	Bitumen Emulsion	1 contract	1 per contract or material change	MRTS 21
Mix Design-Nominated Mix	Approval of mix and NATA certification. Supplier's documentary evidence and certification	1 mix per contract	1 per mix	
Production Mix	Temperature Moisture Content Grading Binder Content	1 per truck load SC6.4.6.13 Asph included as sepa Additionally, max hr shift's producti	altic concrete as rate table below. lot size one 12	
Laying and Compaction	Temperature Levels	1 day's laying per site 1 day's laying	1 per truck load	Measure Survey
	Shape	per site 1 day's laying	per 25m 10 per 200m* lane	3m Straight Edge
	Relative Compaction/Layer Thickness	1 day's laying		As per MRTS30 Compaction requirements or Nuclear Density Meter

Note—* or part thereof, per lot.

Table SC6.4.5.3.8 Minimum testing frequencies for asphalt production

Quantity of Asphalt in production lot	Minimum Frequency of Testing
Less than 100 tonnes	MRTS 30
101 to 300 tonnes	MRTS 30
301 to 600 tonnes	MRTS 30
Over 600 tonnes	MRTS 30

Table SC6.4.5.3.9 Ready-mixed concrete production and supply (SC6.4.6.14 and SC6.4.6.15)

Activity	Key Quality Verification Requirements	Maximum Lot Size	Minimum Test Frequency	Test Method
Raw Materials Supply	Material Quality—Supplier's documentary evidence and certification of:	1 contract	1 per contract or material change	
	Cement	1 contract	1 per contract or material change	AS 3972
	Flyash	1 contract	1 per contract or material change	AS 3582.1
	Water	1 contract	1 per contract or material change	
	Admixtures	1 contract	1 per contract or material change	AS 1478
	Fine Aggregates (SC6.4.615 only)	1 contract	1 per contract or material change	
	Grading	1 contract	1 per contract or material change	AS1141.11
	Moisture Content	1 contract	1 per contract or material change	
	Sulphate Soundness	1 contract	1 per contract or material change	AS1141.24
	Bulk Density	1 contract	1 per contract or material change	AS 2758.1
	Unit Mass (particle density)	1 contract	1 per contract or material change	AS 2758.1
	Water Absorption	1 contract	1 per contract or material change	AS 2758.1
	Material Finer 2µm	1 contract	1 per contract or material change	AS 2758.1
	Deleterious Material (Impurities/Reactive)	1 contract	1 per contract or material change	AS 2758.1
	Combined Aggregates (SC6.4.6.14 and SC6.4.6.15)	1 contract	1 per contract or material change	
	Grading	1 contract	1 per contract or material change	AS1141.11
	Moisture Content	1 contract	1 per contract or material change	

Activity	Key Quality Verification Requirements	Maximum Lot Size	Minimum Test Frequency	Test Method
,	Wet Strength	1 contract	1 per contract or material change	AS1141.22
,	Wet/Dry Strength Variations	1 contract	1 per contract or material change	AS1141.22
	Sulphate Soundness	1 contract	1 per contract or material change	AS1141.24
	Particle Shape	1 contract	1 per contract or material change	AS1141.14
	Fractured Faces	1 contract	1 per contract or material change	AS1141.18
	Bulk Density	1 contract	1 per contract or material change	AS 2758.1
	Unit Mass (particle density)	1 contract	1 per contract or material change	AS 2758.1
	Water Absorption	1 contract	1 per contract or material change	AS 2758.1
,	Material Finer 75μm	1 contract	1 per contract or material change	AS 2758.1
Raw Materials Supply	Weak Particles	1 contract	1 per contract	AS 2758.1
	Light Particles	1 contract	1 per contract	AS 2758.1
,	Deleterious Materials (Impurities/Reactive)	1 contract	1 per contract	AS 2758.1
	Iron Unsoundness	1 contract	1 per contract	AS 2758.1
	Falling/Dusting Unsoundness	1 contract	1 per contract	AS 2758.1
Mix Design (kerb mix)	Compressive Strength	1 contract mix	1 per mix per contract	AS1012.1, AS1012.8, AS1012.9
	Aggregate Moisture Content	1 contract mix	1 per mix per contract	Q102A, Q102B or Q102D
	Non Conformance - Compressive Strength	Superintendent to determine		AS1012.14
	Consistency - Slump	1 contract mix	1 per mix per contract	AS1012.3.1
	Air Content	1 contract mix	1 per mix per contract	AS1012.4.2 (Method 4.2)
	Shrinkage	1 contract mix	1 per mix per contract	AS1012.13

Table SC6.4.5.3.10 Mass concrete subbase (SC6.4.6.14)

Activity	Key Quality Verification	Maximum	Minimum	Test
	Requirements	Lot Size	Test Frequency	Method
Concrete Supply	Refer to Table SC6.4.3.30			
	Concrete/Air Temperature	50m ³	1 per 50m ³	Measure
	Air Content	50m ³	1 per 50m ³	AS1012.4.2
	All Content	301119	i per Joini	(Method 4.2)
				(1016111004.2)
	Consistency - Slump	50m ³	1 perload	AS1012.3.1
	- Compactibility Index	50m ³	1 perload	AS1012.3.4
	Compressive Strength (7 day)	50m³	1 pair per 50m ³	AS1012.1
				AS1012.8
				AS1012.9
	Compressive Strength (28 day)	50m ³	1 pair per 50m ³	AS1012.1
	Compressive Strength (26 day)	301119	pair per 30iii	AS1012.1 AS1012.8
				AS1012.8 AS1012.9
				A01012.5
	Non Conformance - Compressive	Superintendent		AS1012.14
	Strength	to determine		
Placement	Thickness	50m³	5m grid on plan	Survey and
			area	check with
				subgrade survey
	Construction :	E02	4	Comment and One
	Geometry	50m ³	1 cross section	Survey and 3m
			per 15m	Straight Edge
Curing	Material Quality - Supplier's	1 contract	1 per production	AS1160
	documentary evidence and certification		batch	(Bitumen
	,			Emulsion)
				,
	Application Rate	1 day's work	1 per 1000m ² *	AS3799 - Liquid
				membrane
				forming curing
				compound for
				concrete
Joints	Geometry	50m ³	All joints	Survey

^{*} Note—or part thereof, per lot

Table SC6.4.5.3.11 Plain or reinforced concrete base (SC6.4.6.15)

Activity	Key Quality Verification	Maximum		Test
Concrete Supply	Requirements Refer to Table 6.4.3.30	Lot Size	Test Frequency	wethod
Concrete Guppiy	Trefer to Tuble 6.4.5.56			
	Concrete/Air Temperature	50m³	1 per 50m³	Measure
	Air Content	50m³	1 per 50m³	AS1012.4 Method 2
	Consistency - Slump	50m ³	1 per load	AS1012.3.1
	Mass per unit volume (prior crushing of 7-day specimen)	50m ³	1 per 50m³	AS1012.12.2
	Compressive Strength (7 day)	50m³	1 pair per 50m³*	AS1012.1 AS1012.8 AS1012.9
	Compressive Strength (28 day)	50m³	1 pair per 50m³*	AS1012.1 AS1012.8 AS1012.9
	Non Conformance - Compressive Strength	Superintendent to determine		AS1012.14
Steel Reinforcement	Material Quality - Supplier's documentary evidence and certification	1 contract	1 per production batch	AS4671
	- Splicing (welded)	1 contract		AS1554.3
Placement	Relative Compaction			
	Machine Placed	50m ³	1 per 50m³*	AS1012.14 AS1012.2
	Hand Placed	Area between 2 consecutive const. joints or 50m³ (whichever is the lesser)	·	AS1012.14 AS1012.2
	Thickness	50m³	5m grid on plan area	Survey
	Geometry	50m³		Survey and 3m Straight Edge
Ride Quality	Profile Factor	1000m²	10/lane/lot	3m Straight Edge
Surface Texture	Texture Depth	1000m²	2 per lot	Survey
Curing	Material Quality—Supplier's documentary evidence and certification	1 contract	1 per production batch	AS1160 (Bitumen Emulsion)

	Application Rate	1 day's work	1 per 1000m ^{2*}	AS3799 - Liquid membrane
Joints	Sealant Material Quality Supplier's documentary evidence and certification	1 contract	1 per prod'n batch	
	Geometry	50m ³	All joints	Survey

^{*} Note—or part thereof, per lot

Table SC6.4.5.3.12 Bituminous microsurfacing (SC6.4.6.17)

Activity	Key Quality Verification Requirements		Minimum Test Frequency	Test Method
Materials Supply	Material Quality—Supplier's documentary evidence and certification of:			
	Bitumen (prior to emulsification)		1 per contract or change in material	AS2008
	Bitumen Emulsion Residual Binder Content (Residue from Evaporation)		2 per bulk delivery	AS1160, App.D
	Mineral Aggregates- Degradation Factor		1 per contract or 6 month period	AS1141.25
	- Los Angeles Value	1 contract	u	AS1141.23
	- Aggregate Wet Strength	1 contract	ű	AS1141.22
	- Wet/Dry Strength Variation	1 contract	ű	AS1141.22
	- Polished Aggregate Friction Value	1 contract	и	AS1141.42
	- Sand Equivalent	1 contract	ű	AS1289.3.7.1
	Mineral Filler	1 month's prod'n	и	AS2350
	Combined Aggregate Grading	1 contract	и	AS1141.11 AS1141.12
Mix Design— Nominated Mix	Approval of mix and NATA certification—Supplier's documentary evidence and certification	1 contract	1 per mix	
Production Mix	Grading	1 day's prod'n or 50m³ (whichever	2 per 50m ^{3*}	AS2891.3.1
	Residual Binder Content	,	2 per 50m³*	AS2891.3.1
Laying	Levels	1 layer, max 200m ³	1 cross section per 15m	Survey
	Surface Quality	1 layer, max 200m ³	10 per 100m* lane length	3m Straight Edge
Note—or part thereof, pe				

^{*} Note—or part thereof, per lot

Table SC6.4.5.3.13 Segmental paving (SC6.4.6.18)

Activity	Key Quality Verification Requirements	Maximum Lot Size		Test Method
Materials Supply	Material Quality— Supplier's documentary evidence and certification of:			
	Concrete Segmental Paving Units	1 contract	1 per contract	AS/NZS 4455
	Clay Segmental Paving Units	1 contract	1 per contract	AS/NZS 4455
	Bedding Sand - Grading	1 contract	1 per contract or change in material	AS1141.11
	Joint Filling Sand - Grading	1 contract	1 per contract or change in material	AS1141.11
Base	Geometry	One layer 5000m², max 1 day's placement	One cross section per 25m	Survey
	Surface Quality	"	10 per 200m ² or lot	3m Straight Edge
Edge Restraints	Refer SC6.4.6.28 Minor Concrete Work	1 day's placement	1 per 10 lin m	Measure/Survey
Laying Paver Units	Joint Width	1 day's placement	All joints	Measure
	Geometry	1 day's placement	One cross section per 15m	Survey
	Surface Quality	1 day's placement	10 per 200m ² or lot	3m Straight Edge

Table SC6.4.5.3.14 Minor concrete works (SC6.4.6.28)

1 per contract or material change

1 per contract or material change

1 per contract or material change

Activity	Key Quality Verification Requirements	Maximum Lot Size	Minimum Test Frequency	Test Method	
Subgrade	Compaction	1000 lin m or 1000m ²		AS1289.5.4.1	
Gravel Subbase Construction	Compaction	1 days placement	1 per 100 lin m or 100m ²	AS1289.5.4.1	
	Subbase Geometry	1 days placement	1 per 25 lin m	3m Straight Edge	
Steel Reinforcement	Material Quality—Suppliers documentary evidence and certification	1 delivery	1 per production batch	AS4671	
Fibre Reinforcement concrete	Requirements as per SC6.4.6.28.6(1) - Reinforcement of concrete (Minor concrete works)				
Ready-Mixed Concrete Supply	Material Quality—Suppliers documentary evidence and certification	1 contract	1 per mix type		
	Consistency - Slump	15m³	1 per load	AS1012.3.1 (Method 1)	
	Compressive Strength (7 and 28 day)	15m³	2 pairs per15m ³	AS1012.1, AS1012.8, AS1012.9	
	ALL TESTING—MINIMUM LOT SIZE 3m³. No testing on loads less than 3m³ if supplier can provide documentation of in production testing.				
Raw Materials Supply	Material Quality - Supplier's documentary evidence and certification	1 contract	1 per contract or material change		
	Cement	1 contract	1 per contract or material change		
	Water	1 contract	1 per contract or material change		
	Admixtures	1 contract	1 per contract or material change		

Activity			Minimum Test Frequency	Test Method
•	Fine Aggregrates			
	Grading	1 contract	1 per contract or material change	
	Moisture Content	1 contract	1 per contract or material change	
	Bulk Density	1 contract	1 per contract or material change	
	Water Absorption	1 contract	1 per contract or material change	
	Mineral Finer 2μm	1 cantract	1 per contract or material change	
	Deleterious Material (Impurities/Reactive)	1 contract	1 per contract or material change	
	Coarse			
	Aggregate Grading	1 contract	1 per contract or material change	
	Moisture Content	1 contract	1 per contract or material change	
	Crushing Value	1 contract	1 per contract or material change	
	Soundness	1 contract	1 per contract or material change	
	Particle Shape	1 contract	1 per contract or material change	
	Bulk Density	1 contract	1 per contract or material change	
	Unit Mass (particle density)	1 contract	1 per contract or material change	
	Water Absorption	1 contract	1 per contract or material change	
	Mineral Finer 75 μm	1 contract	1 per contract or material change	
	Weak Particles	1 contract	1 per contract or material change	
	Light Particles	1 contract	1 per contract or material change	

Activity	Activity Key Quality Verification Requirements		Minimum Test Frequency	Test Method
	Deleterious Materials (Impurities/Reactive	1 contract	1 per contract or material change	
	Iron Unsoundness	1 contract	1 per contract or material change	
	Fall/Dusting Unsoundness	1 contract	1 per contract or material change	
	Percentage Wear	1 contract	1 per contract or material change	
Concrete Supply (Mixing at site)	Consistency - Slump	15m³	1 per load	AS1012.3.1
	Compressive Strength (7 days) Compressive Strength (28 days)	15m³ 15m³	2 pairs per15m ³ or part thereof, 1 pair for 7 day test and the other pair for the 28 day test	AS1012.8
Concrete Placement	Finished Levels	15m³	1 cross section per 15m	Survey and 3m Straight Edge
	Surface Dimensions	Single fabrication	As required to confirm design dimensions	Measure
	Finishing of unformed surfaces Geometry	15m³	1 cross section per 15m ³	Survey and 3m Straight Edge
	Joints - Geometry	50m³	All joints	Survey
Curing	Material Quality - Supplier's documentary evidence and certification	1 contract	1 per production batch	AS3799
	Application Rate	1 day's work	1 per 1000m ^{2*}	
Backfilling	Material Quality			
	Maximum particle size	1 contract/ material type	1 per 200m³	Q103
	Plasticity Index	1 contract/ material type	1 per 200m ³	AS1289.3.3.1
	Compaction	1 days work or max 200m ²	1 per 200m²	AS1289.5.4.1
Sprayed Concrete	Test Panels and Cores	1 contract	3 test panels and 4 cores per mix design	AS1012.4, AS1012.9 AS1012.14

Activity	Key Quality Verification	Maximum Lot	Minimum Test	Test Method
	Requirements	Size	Frequency	
	Compressive Strength Cores	15m³	per 15m³	AS1012.4
				AS1012.9
				AS1012.14
	Curing Material Quality—	1 contract	1 per production	
	Supplier's documentary evidence and		batch	
	certification			

^{*} Note-or part thereof, per lot

Table SC6.4.5.3.15 Pavement markings (SC6.4.6.22)

		Maximum Lot Size	Minimum Test Frequency	Test Method
Materials Supply	Material Quality - Supplier's documentary evidence and certification of:			
	Paint	1 contract	1 per contract or change in material	
	Glass Beads	1 contract	"	
	Thermoplastic Material	1 contract	n n	
	Raised Pavement Markers (including temporary raised pavement markers)	1 contract	п	
Paint Application	Wet Film Thickness	1 contract	1 per site visit	AS 1580.107.3 Or Q513
	Application Rate of Glass Beads	1 contract	1 per contract	SC6.4.6.22 Attachment A
Thermoplastic Application	Cold Film Thickness	1 contract	1 per site visit	Measure by micrometer
	Application Rate of Glass Beads	1 contract	1 per contract	SC6.4.6.22 Attachment A

Table SC6.4.5.3.16 Signposting (SC6.4.6.24)

Activity	Key Quality Verification	Maximum	Minimum	Test
	Requirements	Lot Size	Test Frequency	Method
Materials Supply	Material Quality—Supplier's documentary evidence and certification of:			
	Sign Blanks	1 contract	1 per contract, or change in material	
	Aluminium Extrusion Backing	1 contract	"	
	Retro-reflective Material	1 contract	"	
	Non-reflective Paint	1 contract	n n	
	Non-reflective Sheet Material	1 contract	"	
	Steel Sign Support Structures	1 contract	п	
Concrete Foundations	s Refer SC6.4.6.28			

Table SC6.4.5.3.17 Water reticulation (SC6.4.6.2)

Activity	Key Quality Verification	Maximum	Minimum	Test
	Requirements	Lot Size	Test Frequency	Method
Materials Supply	Material Quality—Supplier's documentary evidence and certification of:			
	uPVC Pipes	1 contract	1 per contract	AS2977
	Ductile Iron Pipes	1 contract		AS2280 and AS2129
,	Copper Pipe	1 contract	1 per contract	AS1432
	Polyethylene Pipe	1 contract	1 per contract	AS1159
	Stop Valves Material	1 contract	•	AS2638 and AS2129
,	Non Return Valves	1 contract	1 per contract	AS3578
	Spring Hydrants	1 contract	1 per contract	AS2544 or AS3952
Siting and Excavation	Geometry	1 line	1 per line	Survey
Bedding	Material Quality			

Activity	Key Quality Verification Requirements	Maximum Lot Size	Minimum Test Frequency	Test Method
	Grading	1 contract		AS2032
Thrust and Anchor Blocks	Refer to Table SC6.4.5.3.14			
Chamber Covers and Frames	Geometry	1 cover/frame	1 percover/frame	survey
Testing of Pipelines	Pressure testing	1 line	1 .	As specified in SC6.4.6.2.5
	Bacteriological testing	1 line	'	As specified in SC6.4.6.2.5(3) and (4)
Backfill and Compaction	Compaction	1 line		AS1289.5.7.1, AS1289.5.4.1
Switchgear and Control gear Assembly	Electrical function	each installation	1 factory test per installation	AS3439
Commissioning of Pumping Station	Certification testing of electrical installation in accordance with relevant Australian Standards	1 installation	1 per installation	

Table SC6.4.5.3.18 Sewerage system (Construction specification SC6.4.6.3)

Activity	Key Quality Verification Requirements	Maximum Lot Size	Minimum Test Frequency	Test Method
Materials Supply	Material Quality—Supplier's documentary evidence and certification of:	201 0120	rocerroquoncy	illioniou
	uPVC Pipes	1 contract	1 per contract	AS1477
	Ductile Iron Pipes	1 contract	1 per contract	AS2280 and AS2129
	Vitrified Clay Pipes	1 contract	1 per contract	AS1741
	Precast Access Chambers	1 contract	1 per contract	AS4198
Siting and Excavation	Geometry	1 line/structure	1 per line/ structure	Survey
Bedding	Material Quality Grading	1 contract	1 per contract per source	Q103
Concrete Bedding	Refer Table SC6.4.5.3.14			

Activity	Key Quality Verification Requirements	Maximum Lot Size	Minimum Test Frequency	Test Method
Laying and Jointing of Pipes, Access Chambers, Structures	Geometry	1 line	1 per line	Survey
Thrust and Anchor Blocks	Table SC6.4.5.3.14			
Cast-in-situ Access Chambers	Material Quality Tri-Calcium Aluminate Content Fineness Index Minimum Cement Content	1 contract 1 contract 1 contract	1 per contract per source	AS3972 AS3972 AS3972
Acceptance Test of Gravitation Mains and Access Chambers	Compressed Air Testing	1 line	1 per line	As specified SC6.4.6.3.4
Testing of Rising Mains	Hydrostatic test pressure	1 line	1 per line (max 1000m)	As specified in SC6.4.6.3.4(10)
Backfill and Compaction	Compaction	1 line	1 per 2 layers max 100m ²	AS1289.5.7.1, AS1289.5.4.1 per SC6.4.6.3(24)
Switchgear and Control gear Assembly	Electrical Compliance	each installation	1 factory test per installation	AS3439
Commissioning of Pumping Station	Certification testing of electrical installation in accordance with relevant Australian Standards	1 installation	1 per installation	As specified in SC6.4.6.3.5(9)

SC6.4.5.3 Attachment B Random sampling

(1) General

Random sampling of test locations shall be used to control relative compaction of each layer of (which are generally rectangular in area):

- (a) earthworks;
- (b) selected material zone; and
- (c) stormwater drainage.

The number of samples (n) per lot shall be as indicated in the specific sub-sections which are summarised in SC6.4.5.3 Attachment A.

(2) Locations

Sampling locations within a lot for the control of relative compaction shall be determined as follows:

- representing the lot as a rectangle, sub-divide the lot lengthwise into equi-area sub-lots in accordance with the number of samples selected (n) in accordance with Table SC6.4.5.3.19;
- (b) establish six grid lines within the lot, as illustrated in Figure SC6.4.5.3.3;
- (c) throw a die to select a number between 1 and 6. This determines which grid line to use for the sample location in sub-lot 1;
- (d) throw die to select a group (1-6) in Table SC6.4.5.3.19;

- (e) throw die twice to select two random numbers (between 1 and 6) for row and column in Table SC6.4.5.3.19 and obtain random fraction R;
- (f) length co-ordinate for sample location in Sub-lot 1 = RL/n; and
- (g) for sample location in next sub-lot:
 - (i) add L/n to previous length co-ordinate; and
 - (ii) add 1 (on a cycle of 6) to previous grid line.




Figure SC6.4.5.3.3 Sampling locations for rectangular lot

Table SC6.4.5.3.19 Table of random fractions

GROUP	ROW			COL	UMN		
		(1)	(2)	(3)	(4)	(5)	(6)
(1)	(1)	0.78178	0.45467	0.00347	0.27296	0.00020	0.36517
, ,	(2)	0.59678	0.67931	0.25434	0.59054	0.32444	0.41504
	(3)	0.14464	0.17269	0.61154	0.18291	0.83242	0.50776
	(4)	0.89010	0.44764	0.07451	0.20428	0.49513	0.91440
	(5)	0.91941	0.47726	0.33160	0.30670	0.65114	0.36852
	(6)	0.51085	0.38148	0.22169	0.66578	0.67050	0.69559
(2)	(1)	0.81891	0.48626	0.88892	0.82994	0.16941	0.81528
, ,	(2)	0.37410	0.60232	0.12070	0.79017	0.32981	0.34908
	(3)	0.45921	0.15648	0.58052	0.37413	0.08124	0.97145
	(4)	0.86614	0.94719	0.78872	0.91972	0.45149	0.15107
	(5)	0.26590	0.41140	0.95477	0.81267	0.24018	0.07324
	(6)	0.95205	0.39438	0.73697	0.59427	0.71146	0.00575
(3)	(1)	0.18694	0.36502	0.17828	0.84312	0.57003	0.58583
	(2)	0.91211	0.86936	0.43030	0.27672	0.47393	0.10342
	(3)	0.80714	0.34295	0.00775	0.90855	0.33368	0.21842
	(4)	0.67579	0.92686	0.18005	0.00645	0.11256	0.05278
	(5)	0.03184	0.69876	0.16676	0.43346	0.86992	0.03275
	(6)	0.15623	0.02905	0.72763	0.19095	0.80847	0.39729
(4)	(1)	0.72109	0.17970	0.22505	0.35561	0.98935	0.27818
	(2)	0.37348	0.19381	0.43331	0.75033	0.99963	0.42232
	(3)	0.12129	0.32386	0.56705	0.87165	0.84460	0.92955
	(4)	0.54948	0.08844	0.47061	0.78419	0.18731	0.93485
	(5)	0.15097	0.44967	0.48759	0.84161	0.19212	0.05146
	(6)	0.32360	0.66850	0.99382	0.94050	0.96449	0.96217
(5)	(1)	0.68091	0.54191	0.10910	0.94237	0.23161	0.15167
	(2)	0.97121	0.83626	0.70896	0.45296	0.69475	0.11264
	(3)	0.19723	0.98260	0.57429	0.94789	0.64457	0.20809
	(4)	0.84036	0.14095	0.29451	0.40256	0.34521	0.64924
	(5)	0.97500	0.98056	0.82276	0.97130	0.77329	0.89855
	(6)	0.83244	0.30828	0.06882	0.68471	0.71081	0.91649
(6)	(1)	0.75892	0.29685	0.70044	0.91238	0.53356	0.45239
	(2)	0.13229	0.19701	0.36074	0.32254	0.62045	0.26691
	(3)	0.34789	0.22179	0.91891	0.87651	0.91011	0.97469
	(4)	0.97211	0.68943	0.12831	0.50006	0.20793	0.61151
	(5)	0.24954	0.17809	0.56093	0.51524	0.69135	0.68967
	(6)	0.10062	0.11852	0.47089	0.64765	0.44644	0.35548

SC6.4.5.3 Attachment C Method statement requirements General

- (1) Method statements are required to describe the key steps and sequence in the construction activities, how and by whom each step shall be undertaken and what materials and equipment shall be used. Method statements may include a flow chart to clarify the sequence of key steps. One or more method statements may address a construction activity.
- (2) Each method statement will be supported by a check list which shall identify relevant inspections, test points, materials requirements and hold points. Each requirement on the check list will have an officer responsible

- identified and will require the nominated officer to sign off the requirement so indicating its satisfactory
- (3) Method statements and check lists shall be compatible with the appropriate Inspection and test plan. Check lists will be completed for each lot of work during construction and compiled with other documents to comprise the quality register.
- (4) The Contractor shall submit method statements and check lists to describe the key steps in those construction activities listed below that are identified with a preceding asterisk (*).

Item	Enter *	Activity	Sub-section Number
	here if		
	required		
1		Control of Traffic	SC6.4.6.30
2		Temporary Roadways and Detours	SC6.4.6.30
3		Clearing and Grubbing	SC6.4.6.11
4		Earthworks - Cut	SC6.4.6.10
5		Earthworks - Unsuitable Material	SC6.4.6.10
6		Earthworks - Embankment	SC6.4.6.10
7		Compaction and Quality Control	SC6.4.6.10
8		Siting, Excavation, Bedding, Backfilling and Compaction of Stormwater Drainage	SC6.4.6.4
9		Installation of Pipe Drainage	SC6.4.6.6
10		Installation of Precast Box Culverts	SC6.4.6.7
11		Siting and Installation of Drainage Structures	SC6.4.6.5
12		Construction of Lined Open Drains including Kerb and Gutter	SC6.4.6.9
13		Stabilisation of Pavement or Subgrade Materials	SC6.4.6.19
14		Provision of Subsurface Drainage as subsoil drains, pavement drains or free draining layer	SC6.4.6.20-21, SC6.4.6.8
15		Construction of Flexible Pavement Layers	SC6.4.6.12
16		Construction of Concrete Pavement Layers	SC6.4.6.14-15
17		Construction of Asphaltic Concrete Pavement Layers	SC6.4.6.13
18		Sprayed Bituminous Surfacing	SC6.4.6.16
19		Bituminous Microsurfacing	SC6.4.6.17
20		Construction of Segmental Paving	SC6.4.6.18
21		Pavement Marking	SC6.4.6.22
22		Minor Concrete Works	SC6.4.6.28
23		Landscaping	SC6.4.6.28

SC6.4.5.3 Attachment D Minimum inspection and test plan

Table SC6.4.5.3.20 Water supply-hold points

Clause title/ Item	Requirement	Notice for inspection	Release by		
Materials	Materials				
	Submit alternative products and materials for approval.	2 weeks before ordering	Council (Water Authority)		
Pipeline construction					
General-Work accreditation	•	1 week prior commencement of work	Superintendent		
•	Approval of the proposed alignment from the Water Authority.	1 week	Council (Water Authority)		
	Approval from relevant Authority for the excavation.	1 week	Superintendent		

Clause title/ Item	Requirement	Notice for inspection	Release by
Minimum Trench Width		1 week	Superintendent
for Pipelines-Excavation	or Owner prior to		·
across paved or improved	commencing any excavation		
surfaces	across paved or improved		
	surfaces.		
Pipe Bedding-Trench	Present the completed	2 working days	Superintendent
completed	excavated trench prior to		
	pipe laying, jointing and		
	bedding.		
Laying and Jointing of	Submit method statement	2 working days	Superintendent
Pipes-Existing asbestos	for approval.		
cement pipe cutting and			
disposal			
Pipe testing and restoration			
Testing of Pipelines	Conduct pressure testing.	7 days	Superintendent and Council
Testing of Pipelines-	Conduct pressure testing	3 days	Superintendent and Council
unsatisfactory test results,	upon completion of		
defects and	rectification work.		
leakage			
Backfill and Compaction-		2 working days	Superintendent
Completion of work	pipes for approval prior to the		
	commencement of trench		
	backfilling.		
Restoration of Surfaces	Restore progressively and as	2 working days	Superintendent
	soon as possible after the		
	section of works is		
	completed.		
Pump stations	T		ı
Pumps	Provide written warranty from	2 weeks before ordering	Superintendent
	the manufacturer for		
	approval.		
Electrical Compliance-	1 '''	1 week	Superintendent
ompliance	compliance-Test certificate.		
with required standard			
	Submit underground cabling	2 weeks	Superintendent
of underground cabling	requirements and route for		
- 1	approval.	4	NA
Testing and	Submit required test results.	n week	Water Authority and
Commissioning of Pump			Superintendent
Station-Compliance with			
the Specification			
Requirements	Cive notice of intention to	O weeks	Motor Authority and
Testing and		2 weeks	Water Authority and
Commissioning of Pump	undertake commissioning.		Superintendent
Station-Commissioning	Provide pre-commissioning record sheets.		
Construction compliance	rocora onocio.		
Works-as-executed	Submit work-as executed	2 weeks before operating	Water Authority and
	drawing and Operating and	Joing Dollar operating	Superintendent
Maintenance Manuals	Maintenance Manuals.		
			1

Table SC6.4.5.3.21 Water supply-witness points

Note—the Contractor must notify the Superintendent and/or council of impeding works, where the option of attendance may be exercised by the Superintendent and council.

Clause title/ Item	Requirement	Notice for inspection
Materials		
General–Compliance with	Contractor to inspect material and	2 working days
manufacturers recommendations	products at time of delivery for	
	compliance.	
General-Certification	Provide product or material	3 working days (Pipes and Fittings)
	certification prior to delivery to the	1 week (Valves and Hydrants)
	works.	
Pipeline construction		
Location-Set out	Confirm the set out locations prior to	3 working days
	construction.	
Crossings-Crossings authority	Approval from relevant Authority and	2 weeks
approvals	payment of fees.	
Earthworks-Open excavation	Contractor to provide appropriate	Progressive
	safety measures for open excavation.	
Laying and Jointing of Pipes-	Contractor to present to the	Progressive
Inspection prior laying	Superintendent materials prior laying	
	(if required).	
Pipe testing and restoration		
Disinfection and Flushing of	Provide evidence of compliance with	2 working days upon completion of
Pipelines	this requirement.	activity.
Restoration of Surfaces-Disposal of	Superintendent approval is required	2 working days progressive
surplus material	prior spreading/disposal.	

Table SC6.4.5.3.22 Sewerage systems-hold points

Clause title/ Item	Requirement	Notice for inspection	Release by	
Materials Control of the Control of				
General	Submit alternative products and materials for approval.	2 weeks before ordering	Superintendent	
Pipeline construction				
General-Work accreditation	Provide proof of accreditation for approval.	1 week prior commencement of work	Superintendent	
General –Change of Pipeline Alignment	Approval of the proposed alignment from the Sewer Authority.	1 week	Superintendent and Council (Sewer Authority)	
Earthworks-Prior Excavation	Approval from relevant Authority for the excavation.	1 week	Superintendent	
Excavation near underground services— Protection of other services	Submit for approval give notice of any interference to the works caused by an existing service and submit a proposed work method statement.	1 week	Superintendent	
Pipe Bedding-Foundation Condition/Water Charged Ground	Notify Superintendent and confirm method of foundation support from the designer.	Progressive	Superintendent	
Wrapping Pipelines– Damage to sleeving	Rectify any damage to sleeving before backfilling trench.	Progressive	Superintendent	

Clause title/ Item	Requirement	Notice for inspection	Release by
Bedding and Backfill	Present the laid and jointed	•	Superintendent
Compaction Requirements-		- g •	
1 -	trench backfilling.		
of pipeline laid and jointed.	ar or row base a manage		
Bedding and Backfill	Submit proposalfor	1 week	Superintendent
Compaction	construction of	T WOOK	Caperinterident
-	embankments.		
Pipeline testing and restora			
Acceptance Test of	Present all sewers and	1 week	Superintendent and Sewer
Gravitation Sewers and	maintenance holes for	. week	Authority
Maintenance Holes-	acceptance testing.		, tallionly
acceptance Testing	acceptance teeming.		
Acceptance Test of	Submit proposed alternative	1 week	Superintendent and Sewer
Gravitation Sewers and	testing regime for approval.	I WOOK	Authority
Maintenance	lesting regime for approvain		, tallionly
Holes-Hydrostatic testing			
Connection to Existing	Submit request to connect	3 weeks before connection	Superintendent and Sewer
Sewers	to the existing sewer and	weeks before connection	Authority
	give notice of works		, tallionly
	including any affected		
	occupants.		
Testing of Rising	Present rising main for	1 week	Superintendent and Sewer
Mains-Pressure Test	acceptance testing.	T WCCK	Authority
Restoration of Surfaces-	Restore progressively and	2 working days	Superintendent
	as soon as possible after	working days	Superintendent
Original condition requirement	the section of works is		
	completed.		
Pump stations	compicted.		
General-Authorised	Submit alternative products	2 weeks before ordering	Superintendent
products and materials	and materials for approval.	weeks before ordering	Caperinterident
Pumps		Upon delivery on site	Superintendent
_	the equipment.	opon delivery on site	Capeninenaeni
Electrical Compliance-	Supply a proof of	1 week	Superintendent
Compliance with required	compliance – Test	T WOOK	Capelinterident
standard	certificate.		
Electrical Installation-	Submit underground cabling	2 weeks	Superintendent
Route of	requirements and route for	2 WCCK3	Superinterident
underground cabling	approval.		
Testing and	Submit required test results.	1 week	Sewer Authority and
Commissioning of Pump	Cabillit required testresults.	II WEEK	Superintendent
Station-Compliance with the			Caponinania
Specification Requirements			
Testing and	Give notice of intention to	2 weeks	Sawar Authority and
Commissioning of Pump	undertake commissioning.	IT MCCV9	Sewer Authority and Superintendent
Station—Commissioning	Provide pre-commissioning		Superintendent
otation—commissioning	record sheets.		
Practical Completion of	Fulfil all the requirements for	2 wooks	Superintendent
Pump Station	issuance of Certificate of	IT MCCV9	Superintendent
rump station	Practical Completion.		
Construction compliance	radioar dompielion.		
Works-as-executed details	Submit work as avacuted	1 wook hofore energting	Sower Authority and
		1 week before operating	Sewer Authority and
and Operation and	drawing and Operating and Maintenance Manuals.		Superintendent
Maintenance Manuals	iviaintenance ivianuais.		

Table SC6.4.5.3.23 Sewerage systems-witness points

Clause title/item	Requirement	Notice for inspection
Materials		
General-Compliance with	Contractor to Inspect material and	2 working days
Manufacturer's recommendations	products at time of delivery for	
	compliance.	
General-Certification	Provide product or material	3 working days (Pipes and Fittings)
	certification prior to delivery to the	1 week (Valves)
	works.	
Pipeline construction		
Crossings—Crossings Authority	Approval from relevant Authority and	2 weeks
approvals	payment of fees.	
Earthworks-Open excavation	Contractor to provide appropriate	Progressive
	safety measures for open excavation	
Bedding and Backfill Compaction	Provide NATA certified test results for	2 working days progressive
Requirements-NATA	all testing.	
Thrust and Anchor Blocks for	Give notice if the allowable bearing	1 week
Rising Main-Verification of Bearing	pressure of the ground and the design	
Pressures	pressure of the pipeline differ from	
	actual pressures on site.	
Pipeline testing and restoration		
General-Initial Tests (Sewers and	Give notice prior commencement of	2 days progressive
Maintenance Holes)	initial testing.	
Ovality Test and CCTV Inspection-	Submit proposal for deflection testing	1 week (Ovality Test)
Deflection testing and	(Ovality Test).	2 days upon completion of inspection
pipeline verification	Submit CCTV Results.	
Acceptance Test of Gravitation	Submit acceptance test results.	Progressive
Sewers and Maintenance Holes		
Visual Inspection and	Submit method of infiltration testing.	1 week
Measurement of Infiltration–		
Infiltration testing		
Testing of Rising Main	Submit acceptance test results.	Progressive
Restoration of Surfaces-Disposal of	1 .	2 working days progressive
surplus material	prior to spreading/disposal.	
Pump stations		
General - Conformance with		2 working days
manufacturers recommendations	of delivery.	
Electrical Compliance-approval of	Submit all design drawings and	2 weeks before ordering
Electrical Compliance-approval of all design and materials	Submit all design drawings and materials to each Authority having jurisdiction for approval.	2 weeks before ordering

Table SC6.4.5.3.24 Stormwater drainage-hold points

Clause title/Item	Requirement	Notice for inspection	Release by
Construction			
Temporary drainage– Erosion and Sediment Control	Confirmation of accepted project ESCP and completion of erosion and sedimentation control measures.	1 week prior to site commencement	Superintendent and Council
Siting of Culverts-Survey set-out	Submit survey set-out of culvert inlets and outlets for approval.	1 week prior to proceeding	Superintendent
Siting of Culverts-Changes by Contractor	Submit proposed changes for approval.	1 week prior to proceeding	Superintendent
Excavation-Public utilities	Obtain approval for adjacent excavation with relevant authorities.	1 week prior to proceeding	Superintendent
Construction traffic- Protection measures	Submit certification and verification of protection measures.	3 working days	Superintendent

Table SC6.4.5.3.25 Stormwater drainage-witness points

Note—the Contractor must notify the Superintendent and/or council of impeding works, where the option of attendance may be exercised by the Superintendent and council.

Clause title/Item	Requirement	Notice for inspection
Construction		
Excavation-Notice	Identify unsuitable materials and	progressive
	inadequate support material for	
	removal and disposal at the foundation	
	level of the structure.	
Backfilling-In situ concrete	Do not backfill against in situ concrete	progressive
structures	structures within 14 days of concrete	
	placement.	
Backfilling-Tolerance	Check shape of culvert during	progressive
	backfilling.	
Compaction adjacent to culverts or	Inform the Superintendent prior	2 working days before proceeding
drainage structures	rectification any damage.	

Table SC6.4.5.3.26 Drainage structures-hold points

Clause title/Item	Requirement	Notice for inspection	Release by			
Construction	Construction					
Precast Units-Product	Submit details of precast or	1 working day and 3 working	Superintendent			
drawings and Quality	proprietaryitemsforapproval	days before delivery				
	and Submit quality test	respectively				
	results.					
Excavation	Excavation and compaction	1 working day	Superintendent			
	of foundation as					
	documented.					
Backfill-Commencement	Obtain approval for	1 workday day	Superintendent			
	commencement.					

Table SC6.4.5.3.27 Drainage structures-witness points

Note—the Contractor must notify the Superintendent and/or council of impeding works, where the option of attendance may be exercised by the Superintendent and council.

Clause title/Item	Requirement	Notice for inspection
Construction		
Headwalls and Wingwalls - Batter	If dimensions on drawings are unable	3 working days
retention	to satisfy batter retention, notify the	
	Superintendent.	
Precast units	Give notice of installation of precast	1 week
	pits and junction boxes.	
Construction	Submit for approval part omission of	3 working days
	concrete lining.	

Table SC6.4.5.3.28 Pipe drainage-hold points

Clause title/Item	Requirement	Notice for inspection	Release by
Common requirements			
General-Material Certification	Submit conformance certificate and other relevant manufacturer quality		Superintendent
General-Alternative materials	documentation. Submit full product details in accordance with AS/NZS 2566.1.	4 weeks prior to commencing work	Superintendent and Council
General-Backfilling	Present the completed installation and jointed pipes for inspection.	Progressive before backfilling	Superintendent and Council
General-Protection of structures	Submit design proposal for protective measures for approval.	3 days prior	Superintendent and Council
Steel pipes and pipe arche	es		
Materials and Surface Treatment	Engineer's certification for the pipe materials and surface treatments.	Prior to practical completion	Superintendent
UPVC pipes			
Materials-Proprietary product with external diameter of ≥450mm	Submit for approval prior to construction.	4 weeks	Superintendent and Council

Table SC6.4.5.3.29 Pipe drainage-witness points

Clause title/Item	Requirement	Notice for inspection
Precast reinforced concrete and fib	re reinforced concrete pipes	
Excavation-Wide Trench Condition	If deemed as a wide trench, confirm	Progressive
	appropriate pipe strength/trench	
	support.	
Bedding	Source of bedding material -advise	Progressive
	Superintendent.	
Bedding-Cementitious stabilisation	Provide if erosion of bedding material	1 week
	may occur.	

Table SC6.4.5.3.30 Precast box culverts-hold points

Clause title/Item	Requirement	Notice for inspection	Release by
Materials			
Culvert Units, Link and Base Slabs	Submit certificate of conformance.	3 working days prior to dispatch	Superintendent
Proof load testing	Submit certificate and test results.	3 working days prior to dispatch	Superintendent
Construction			
Construction of coffer dams	Submit construction details for approval.	1 week prior to construction	Superintendent
•	Inspection of foundation and approval of proposed bedding.	2 days before placing material	Superintendent
•	Present joints and seals for before backfilling.	1 working day	Superintendent
culvert —Constraint	Do not load base slab until strength has reached 20 MPa.	1 working day	Superintendent

Table SC6.4.5.3.31 Precast box culverts-witness points

Note—the Contractor must notify the Superintendent and/or council of impeding works, where the option of attendance may be exercised by the Superintendent and council.

Clause title/Item	Requirement	Notice for inspection
Materials		
Handling, Delivery and Storage	Inspect box culvert units for	1 week prior to installation
	conformance.	
Construction		
Coffer Dams—Timber or bracing	Inspect removal of bracing materials.	1 working day
removal		
Installation of Precast in situ base	Attainment of concrete minimum	1 working day
slabs	compressive strength.	

Table SC6.4.5.3.32 Drainage mats-hold points

Item/Clause title	Requirement	Notice for inspection	Release by	
Type A mats / Type B mats	Гуре A mats / Type B mats			
Geotextile, Damaged	Approval of condition or	1 working day before next	Superintendent	
geotextile	repair of geotextile.	activity		
Filter material, Thickness	Approval of thickness and	3 working days before	Superintendent	
	layers of filter material.	placing filters		

Table SC6.4.5.3.33 Drainage mats-witness points

Item	Requirement	Notice for inspection
Type A mats /Type B mats		
Filter material, Protective layer	Inspection of placement of protective	3 working days before placing
	layer over mat extension.	materials
Discharge, Outlets	Inspection of outlet proposals.	7 days before set-out of layers

Table SC6.4.5.3.34 Open drains-hold points

Clause title/Item	Requirement	Notice for inspection	Release by		
Pre-construction planning	re-construction planning				
Provision for traffic	Submit Traffic Guidance	2 weeks prior to site	Superintendent		
	Scheme for approval.	commencement			
Temporary drainage	Submit details of	2 weeks prior to site	Superintendent		
	procedures/devices for	commencement			
	approval.				
Materials					
Proprietary Products	Submit proprietary products	7 days prior to	Superintendent		
	and manufacturer's	commencement on site			
	instructions.				
Gabions/Wire mattresses	NATA compliance	7 days prior to	Superintendent		
	certificates for proposed	commencement on site			
	Gabions.				
Rock fill material	NATA compliance	7 days prior to	Superintendent		
	certificates for proposed rock	commencement on site			
	fill material.				
Geotextile	NATA compliance	7 days prior to	Superintendent		
	certificates for proposed	commencement on site			
	Geotextile material.				
Open drains					
Excavation	Approval to divert drain to	1 working day before set-out.	Superintendent.		
	avoid trees and/or rocks.				
Excavation	Location and construction of	1 working day before set-out.	Superintendent.		
	drains to prevent salination.				
Kerb and channel (gutter)					
Foundation	Approval for shape and	1 working day before forming	Superintendent		
	compaction of foundation				
	material.				

Table SC6.4.5.3.35 Open drains-witness points

Clause title/Item	Requirement	Notice for inspection
Open drains		
Excavation	Unsuitable material removal and	Progressive
	disposal.	
Excavation	Spoil site locations.	Prior to placement
Embankment	Embankment compaction and	Progressive
	revegetation.	
Construction	Grade and compaction of open drains.	Progressive
Construction	Proprietary items installed to	Progressive
	manufacturers recommendations.	
Types	Maintain catch drains.	Progressive
Types	Construct minor diversion and contour	Progressive
	drains, table drains, swales and	
	depressed medians.	
Types	Channels preserving the existing	Progressive
	stream bed.	
Lining		
Concrete lining	Instruction on weephole location.	1 working day before concreting.
Concrete lining	Joints and tolerances.	1 working day before concreting.
Stone pitching	Bedding material and placement.	1 working day before concreting.
Kerb and channel (gutter)		
Stormwater outlets	Positive drainage to channel.	Progressive
Vehicular or pedestrian access	Siting, location and bedding	Progressive
	compaction.	
Backfilling and reinstatement		
Backfill behind kerbs	Backfilling timing, material and	1 working day prior to backfilling
	compaction.	
Pavement backfill	Backfill adjacent new gutter material	1 working day prior to backfilling
	and location.	
Rock filled wire mattresses and	Inspection of rockfill material and filling	On completion of works
gabion- Completion	method.	

Table SC6.4.5.3.36 Earthworks-hold points

Clause/subclause	Requirement	Notice for inspection	Release by
Stockpile Sites	Approval to use any	3 working days before	Superintendent
	stockpile site not shown on the Drawings.	stockpiling	
Treatment of Floors of	Present in situ material for	Before ripping commences	Superintendent
Cuttings—Prior ripping floors			
of cuttings	suitability of pavement		
	support.		
Treatment of Floors of	Inspection of compacted	Prior to placing any	Superintendent and Council
Cuttings-Compacting floors	cutting floor.	subsequent layers over the	
of cuttings		completed cutting floor	
Unsuitable material-Floor	Re-present the floor of the	Prior to backfilling with	Superintendent
inspection	excavation after the removal	replacement material	
	of unsuitable material.		
Foundations for	Inspection of the	1 working day prior to next	Superintendent
Embankments	embankment foundation	activity	
	area.		
Foundation for	Inspection and direction for	3 working days before	Superintendent
Embankments-Other	bridging layer where required	proceeding	
Embankments (Bridging			
layer)			
Trimming tops of	Inspection of the completed	Prior to placing any	Superintendent
embankments	surface to receive	subsequent pavement layers	
	subsequent pavement		
	layers.		
Selected material zone	Inspection of the completed	_ ,	Superintendent
	select material zone surface	proceeding	
	prior to placing any		
	subsequent pavement		
	layers.		
Fill adjacent to structures-	Concrete strength required	3 working days prior to fill	Superintendent
General	for early filling to structures.	placement	
Deflection monitoring or	Present the completed work	2 working days before next	Superintendent and Council
proof rolling	for deflection monitoring or	activity	
	proof rolling.		

Table SC6.4.5.3.37 Earthworks-witness points

Clause/subclause	Requirement	Notice for inspection
Natural Surface and Earthworks	Survey method and results, including	At least 7 days notice
Materials	any discrepancies.	
Cuttings-Floors of cuttings	Floors to be no more than 50 mm	1 working day before next activity
	above or below the designed floor and	
	provide suitable support.	
Batters-Excavation beyond the	Minor change in the general slope of	1 working day before next activity
batter line	the batter to suit the site conditions.	
Transition from cut to fill-Terrace	Excavate a terrace for the width of the	1 working day before excavating
	selected material zone to a depth of	terrace
	900 mm below and parallel to the	
	cutting floor.	
Unsuitable Material	Material deemed unsuitable for	Progressive
	embankment or pavement support in	
	its present position.	
Placing Fill for Embankment	Modify grading of fill material to	Progressive
Construction-Rock material	achieve compaction.	
Fill adjacent to	Proposal to use synthetic membrane	3 working days before proposed use
structures-Treatment at weepholes	geotextile.	
Spoil–Haulage disposal	Obtain planning approval and any	3 working days before commencing
	permits.	activity
Borrow-Requirement	Obtain planning approval and any	3 working days before commencing
	permits.	activity

Table SC6.4.5.3.38 Clearing and grubbing-hold points

Clause/subclause	Requirement	Notice for inspection	Release by
Limits of clearing			
Survey	Decision on the removal of	7 days before proposed	Superintendent
	miscellaneous items.	removal	
Extent of clearing	Submit peg out and extent of	7 days before proposed	Superintendent and Council
	clearing survey.	commencement of clearing	
Clearing Operations			
Tagging	Confirm clearing perimeters	7 days before proposed site	Superintendent and
	and mark trees to be	clearing	Authorised Council Officer
	preserved.		
Work near trees noted for	Work method statement for	7 days before proposed	Superintendent
protection	works within the exclusion	works	
	zone.		
Excavation within 4m of	Develop appropriate work	7 days before proposed	Superintendent
tree trunks	methods to avoid damage to	excavation	
	the tree for approval.		
Trees within proposed	Direction to remove or	7 days before proposed site	Superintendent
embankment areas	protect trees within proposed	clearing	
	embankments.		
Unsound trees in road	Direction on removal of trees	7 days before proposed site	Superintendent
reserve	or branches not within the	clearing	
	clearing limits.		
Timber falling on private	Written consent of owner to	Prior to carrying out works	Superintendent
property	leave in place or to enter		
	property to remove.		
Damage	Approval for any	3 working days prior to	Superintendent and
	rehabilitation of vegetation or	carrying out works	Authorised Council Officer
	fauna habitat.		
Grubbing			
Blasting	1	Progressive	Superintendent
	without prior approval.		
Disposal of materials			
Burning of material	1	Prior to burning	Superintendent
	timber and other		
	combustible materials by		
	burning.		

Table SC6.4.5.3.39 Clearing and grubbing-witness points

Clause/subclause	Requirement	Notice for inspection
Existing Utility services-Marking	Locate all underground pipe and	Before commencing any earthworks
	cables.	
Trees to be preserved-Work near	Exclusion zone around protected	Progressive
trees noted for protection	trees.	
Trees to be preserved-Tree	Trees and roots not to be cut or	Progressive
protection	damaged.	
Grubbing–Backfill	Backfill and compact grub holes.	Progressive
Chipping of cleared vegetation-	Stockpile location approval.	Prior to stockpiling
Stockpiling		

Table SC6.4.5.3.40 Flexible pavements-hold points

Clause title/Item	Requirement	Notice for inspection	Release by
Activity plan			,
• •	Prepare and submit	4 weeks before commencing	Superintendent
	pavement plan.	site work	
Inspection, sampling and t	·		
Notification	Written notice for testing	3 working days prior to	Superintendent
	-	testing or inspection	'
	results.		
Materials			
Proposed materials	Prepare and submit	2 weeks before ordering	Superintendent
	schedule detailing material	materials	
	properties including NATA		
	test results and certificate.		
Bound or modified	Complete and submit	2 weeks before ordering	Superintendent
materials	(SC6.4.6.19 Attachment A).	materials	
Variations to approved	Submit details of changes to	1 week before use in works	Superintendent
materials	approved materials.		
Lime modified base and su	ibbase materials		
Lime modification	Submit proposals to modify	2 weeks before placing	Superintendent
	materials.		
Stationary Plant or In-situ	Submit proposals for the in-	2 weeks before activity	Superintendent
lime modification	situ use of hydrated lime or		
	quicklime.		
Spreading			
Underlying layer	Inspection to determine	1 working day before placing	Superintendent
	suitability of underlying	next layer	
	layer.		
Temperature	Submit proposal to proceed		Superintendent
	outside allowable conditions.	placement	
Trimming, compaction and			
Plant	' '	1 week before use	Superintendent
	hand operated plant.		_
Subsequent layers	Submit completed test	1 working day before placing	Superintendent
		next layer	
Acceptance of compaction			
Lots for acceptance	Submit compaction test	1 working day after testing	Superintendent
	results.	A consultant data (Control	0
Compaction requirements		1 working day after test	Superintendent
and acceptance	'	results	
Toloranos	tolerances.		
Tolerances	Cultimit lot annual and and	4aulina alambatana araw	Cup a wint a wall a sat
General	Submit lot survey reports.	1 working day before next activity	Superintendent
Action on rejection			
Corrective action-rejected	Submit proposal for	1 working day before next	Superintendent
unbound layers	corrective action.	activity	
Corrective action-rejected	Submit proposal for	3 working days before next	Superintendent
bound layers	corrective action.	activity	
Removal and replacement of rejected course			
Extent of removal	Submit proposal to remove	1 working day before next	Superintendent
	less than full width.	activity	

Clause title/Item	Requirement	Notice for inspection	Release by
Prior to replacement	Give notice for inspection of	1 working day before next	Superintendent
	underlying material.	activity	
Replacement	Submit proposed methods to	1 working day before next	Superintendent
	make good.	activity	
Maintenance before compl	etion of wearing course		
Pavement condition	Dry-back, re-prepare and	3 working days before next	Superintendent and Council
before primerseal	give notice for inspection.	activity	
Opening bound pavement	Give notice of proposed	3 working days before	Superintendent
to traffic	opening to traffic.	proposed opening	

Table SC6.4.5.3.41 Flexible pavements-witness points

uperintendent and council.			
Clause title/Item	Requirement	Notice for inspection	
Delivery to site			
Delivered materials	Give notice for inspection.	Progressive	
Delivery of modified or bound mate	rials		
Delivery of materials	Provide delivery dockets at point of	Progressive	
	delivery.		
Stockpiling of unbound materials			
Location	Give notice of proposed alternative	2 weeks before stockpiling	
	locations.		
Trimming, compaction and curing			
Compaction	Give notice of proposal to use	2 weeks before activity	
	alternative layer thickness.		
Rework	Give notice for inspection of reworked	Progressive	
	wetted up layer.		
Curing of bound materials	Give notice of water curing activities.	Progressive	
Acceptance of compaction			
Nuclear density Meter testing	Give notice of proposal to use Nuclear	1 working day before use	
	density meter.		
Tolerances			
Layer width	Give notice of completion of layer	Progressive	
	width.		
Levels and Surface Trims	Give notice of completed surface	Progressive	
	layer.		

Table SC6.4.5.3.42 Asphaltic concrete-hold points

Clause/subclause	Requirement	Notice for inspection	Release by
Plant	Evidence that plant is registered and insured.	2 weeks before using plant	Superintendent
Delivery—work records	Submission for counter signing.	Each day for daily completion	Superintendent
Asphalt mix design	0		
Approved Mix	Submit approved mix design for Superintendent confirmation.	7 days before using mix	Superintendent
Production Mix— Production Sampling and Testing	Submission of all documented test results.	Within 7 days of delivery of material	Superintendent
Asphalt mixes incorporating RAP	Mixes containing more than 20% RAP to be submitted for assessment.	7 days before using mix	Superintendent
Placing	Present surface prior spreading.		Superintendent
Joints— General	Submit plan of joints location for approval.	7 days before commencing	Superintendent
Preparation of Pavement — Rectification of Pavement Surface	Prepare surface to the satisfaction of the Superintendent.		Superintendent
Laying— Paver	Provide notice of proposed pavers.		Superintendent
Removal and Replacement of Rejected Material	Present surface after removal of the rejected material.		Superintendent

Table SC6.4.5.3.43 Asphaltic concrete-witness points

Clause/subclause	Requirement	Notice for inspection
Plant	Superintendent to assess faulty plant.	Progressive
Production	Superintendent to access the mixing	Progressive
	plant to verify production procedures	
	and the supplier's compliance with the	
	Contractor's Project Quality Manual	
	and Quality Plan.	
Aggregate—General	Source subject to inspection and	3 weeks before importing aggregate
	approval of Superintendent.	

Table SC6.4.5.3.44 Mass concrete subbase-hold points

Clause title/Item	Requirement	Notice for inspection	Release by	
Materials for concrete	Materials for concrete			
Materials	Submit details of concrete mix and materials.	Submit as part of confirmation of nominated mix	Superintendent	
Design and control of cond	rete mixes			
Nominated mix	Submit details of concrete mix and materials including NATA certificates and test results.	21 working days before using the nominated mix (Progressive)	Superintendent and Council	
Variations to nominated mix and materials	Submit details of any change to nominated mix and materials.	21 working days before implementing change	Superintendent	
Conformance for concrete	strength and thickness			
Sampling, curing and testing of fresh concrete	Inspection of sampling procedure.	Progressive	Superintendent	
Acceptance criteria	Submit test results.	Progressive	Superintendent	
Acceptance criteria for cored concrete (non-conformance)	Submit test results.	Progressive	Superintendent	
Production, transport and	consistency of concrete			
Concrete production and transport	Submit proposed work methods.	At least 21 working days before starting	Superintendent	
Placing and finishing conc	rete subbase			
Subbase Paving plan	ubmit as part of Quality lan.	21 working days before starting	Superintendent	
Construction—Placing	ritten notice to commence including trial section).	7 days before starting	Superintendent	
Trial Concrete Subbase —Construction	Inspection of the trial concrete subbase.	1 working day after placing trial section	Superintendent	
Trial Concrete Subbase —Deficient trial section	Provide justification of the methods used in producing deficient work for assessment.	1 working day after deficiency identified	Superintendent	

Table SC6.4.5.3.45 Mass concrete subbase-witness points

Clause title/Item	Requirement	Notice for inspection		
Conformance for concrete strength	Conformance for concrete strength and thickness			
Testing by specimens cut from the	Coring witnessed by Superintendent	3 working days		
work				
Restoration after coring	Inspection of restoration work	3 working days after cutting		
Placing and finishing concrete subbase				
Curing - Efficiency Index	Submit certificate of compliance for	Progressive		
	the curing compound			
Average application rate	Average rate checked by the	Progressive		
	Contractor and certified by the			
	Superintendent			
Bond breaker and spall treatment	Bond breaker and spall treatment			
Treatment of Unplanned Cracks	Check for cracks and repair/reject	Progressive		

Table SC6.4.5.3.46 Plain and reinforced concrete base-hold points

Clause title / Item	Requirement	Notice of inspection	Release by
Design and control of cond	•		,
Nominated mix	Submit details and	21 working days before	Superintendent
	certificates for nominated	using the nominated mix	
	concrete mix and material		
	constituents including NATA		
	certificates and test results		
Variations to nominated mix	Submit details of any	21 working days before	Superintendent
and materials	change to nominated mix	implementing change	
	and materials		
Steel reinforcement			
Placing and cover	Approval of placement and	4 working hours before	Superintendent
requirements	fastening of reinforcing steel	concrete placement	
Production, transport and	consistency of concrete		
Concrete production and	Submit proposed methods	4 weeks before starting	Superintendent
transport	and equipment		
Placing and finishing conc	rete base		
Subbase survey	Work-as-executed survey of	7 days before starting any	Superintendent
	the subbase.	works	
Surface texture		Before texturing	Superintendent
	texturing device and method		
	of texturing		
Trial of Concrete Base	Obtain approval for the trial	5 working days before main	Superintendent
Construction	section	works	
	Provide justification of the	2 working days after	Superintendent
Deficient trial section	methods used in producing	construction	
	deficient work for		
	assessment		
Joints	la		
Permanent sealing—General	Submit proposed method for	4 weeks before installation	Superintendent
	permanent joint sealing		
Slab anchors	lo 1 ''	L	
Excavation	Submit compacted	1 working day before	Superintendent
Tartium of a surrents for a sur	excavated surface	concreting	
Testing of concrete for cor		In	low-sister tout
Sampling	Inspection of sampling	Progressive	Superintendent
A	procedure	D	Our arist as dans
Acceptance criteria	Submit test results	Progressive	Superintendent
Acceptance criteria for cored	Supmit test results	Progressive	Superintendent
concrete	of hoos		
Removal and replacement		7 working days before	Cuparintandant
General	Submit proposed method of		Superintendent
	removal to preserve adjoining	replacement works	
	base and underlying subbase		
	Sunnase		

Table SC6.4.5.3.47 Plain and reinforced concrete base-witness points

Note—the Contractor must notify the Superintendent and/or council of impeding works, where the option of attendance may be exercised by the Superintendent and council.

Witness Points Off Site		
Clause/ subclause	Requirement	Notice of inspection
Materials for concrete		
Aggregates - Storage	Storage and handling to preserve	Progressive
	quality of aggregate	
Steel reinforcement		
General	Provide NATA certificates and	Before delivering to site
	manufacturer's information.	
Bar chairs	Demonstrate load bearing capacity	Before delivering to site
Joints		
Silicone Sealant	Provide NATA certificate and	4 weeks before joint work
	manufacturer's information	
Witness Points On Site		
Joints		
Permanent Sealant	Locations as shown on drawings and	Progressive
	change to spacing	
Placing and finishing concrete base)	
Consistency	Provide slump check test results	Progressive
Protection of Work - Ambient	Provide details of protection methods	Progressive
conditions	for cold or hot weather and rain	
Traffic considerations	Provide traffic management measures	Progressive
Rate of Evaporation and moisture loss	Provide details of precautionary	Progressive
	measures to prevent moisture loss	
	when evaporation rate exceeds	
	prescribed limits	
Paving (Mechanical and Hand Paving)	Construction joint if hand or	Progressive
	mechanical paving is disrupted	
Alignment and Surface Tolerances	Survey of base surface, edge	Progressive
- Assessment of base thickness	alignment and thickness	
Curing - Efficiency Index	Submit certificate of compliance for the	Progressive
	curing compound	
Testing of concrete for compressive	e strength	
Testing of specimens cut from the	Carry out coring in presence of the	
work	Superintendent	
Repair and Restore work after coring	Restore holes with non-shrink	After coring
	cementitious concrete	
Conformance of concrete strength,	compaction and thickness	
Relative Compaction		Progressive
	relative compaction	

Table SC6.4.5.3.48 Sprayed bitumen surfacing-hold points

Clause title/Item	Requirement	Notice for inspection	Release by
Design of bituminous surfa	acing		
Confirmation of Design	Submit the sprayed seal	2 weeks before commencing	Superintendent
and Materials Compliance	design and additional details	work	
	for approval		
Plant	Evidence that plant is	2 weeks before using plant	Superintendent
	registered and insured		

Table SC6.4.5.3.49 Sprayed bitumen surfacing-witness points

Note—the Contractor must notify the Superintendent and/or council of impeding works, where the option of attendance may be exercised by the Superintendent and council.

Clause title/Item	Requirement	Notice for inspection	
Application and rolling of aggregate			
Removal of loose aggregate,	Completion within specified time	Various to allow inspection of	
Loose aggregate particles		performance in conformance with	
		Tables of time limits	
Removal of surplus and waste	Demonstrate that materials are	Progressive	
material	properly disposed		
Protection - New work	Demonstrate that line marking and	Progressive	
	warning signs are in place to protect		
	new work		

Table SC6.4.5.3.50 Bituminous microsurfacing-hold points

Clause title/Item	Requirement	Notice for inspection	Release by	
Mix design	Mix design			
1	Submit details of nominated mix with NATA Certification	7 days before commencing	Superintendent	
Production and paving				
Production mix Bituminous —microsurfacing	Target application rate and nominal layer thickness for approval	7 days before commencing	Superintendent	
Sampling and testing of production mix	Compliance with maximum permitted variations from approved mix	During mixing	Superintendent	
Weather limitations	Cease works if weather conditions are not appropriate	Progressive	Superintendent	
Paving unit calibration	Documentation for detailed calibration	7 days before using paving unit	Superintendent	
Preparation of Pavement	Provide cleaned surface for inspection	1 working day prior to spreading works	Superintendent	
Spreading—Traffic	Capable of carring traffic in short period after slurry surfacing to the approval of Superintendent	One hour after spreading	Superintendent	
Surface texture—Test run	Demonstrate surface texture	1 working day before commencing	Superintendent	
Non-conformance—Materials and finished surfacing	Approval for correction or replacement	1 working day before corrective action	Superintendent	

Table SC6.4.5.3.51 Bituminous microsurfacing-witness points

Note—the Contractor must notify the Superintendent and/or council of impeding works, where the option of attendance may be exercised by the Superintendent and council.

Clause title/Item	Requirement	Notice for inspection
Witness Points Off Site		•
Materials		
Binder—Compliance	Submit NATA test results for the nominated binder	7 days prior to commencing works
Mineral Aggregates—Quality	Submit NATA test results for the nominated mineral aggregates	7 days prior to commencing works
Mineral Filler—Quality Compliance	Submit NATA test results for the nominated binder	7 days prior to commencing works
Witness Point On Site		
Spreading—Clean up	Leave road fixtures in clean and satisfactory condition	Progressive

Table SC6.4.5.3.52 Segmental paving-hold points

Clause title/Item	Requirement	Notice for inspection	Release by
Materials			
General—Nominated materials	Submit segmental paving materials and supplier.	2 weeks before ordering	Superintendent
Construction			
Subgrade Preparation— Dimensions and specification	Present the finished subgrade for approval	1 working day before proceeding	Superintendent
	Present finished subbase for approval	1 working day before proceeding	Superintendent
Base—Dimensions and specification	Present the finished base for approval	2 working days before proceeding	Superintendent

Table SC6.4.5.3.53 Segmental paving-witness points

Item	Requirement	Notice for inspection
Construction		
Opening to Traffic—Inspection	Regularly inspect joints after completion	Progressive

Table SC6.4.5.3.54 Stabilisation-hold points

Clause/subclause	Requirement	Notice for inspection	Release by
Materials proposed for	Submit NATA certificate of	14 days prior to	Superintendent
use in the work	compliance	commencement of works	
Field Working Period	Nominate the specific field	14 days prior to	Superintendent
—Laboratory	working period specified in	commencement of works	
	the Stabilisation Mix Design		
Materials			
Cement—Storage	Re-test cement stored in	2 working days prior to	Superintendent
	excess of 3 months	usage	
Stabilisation Process	Submit a Work Plan	14 days prior to	Superintendent
—Proposed equipment and	nominating proposed plant	commencement	
procedures	and work sequence		
Application of stabilising	Proposals for special	7 days prior to mixing	Superintendent
agent—In situ application	processes of supply of		
	stabilising agent into the		
	mixing bowl		
Mixing—In situ mixing	Demonstration of equipment	7 days prior to production	Superintendent
process	mixing efficiency in trial	stabilisation	
	section		
Trimming and	Work methods to exclude	3 working days prior to	Superintendent
Compaction—Trimming	laminations and slurrying	production stabilisation	
Trimming and	Use of trimmed material as	3 working days prior to	Superintendent
Compaction—Survey	fill or spoil	disposition	
control methods			
Curing—Method statement	Submit details of proposed	As directed	Superintendent
	curing method		
Trial section of stabilised e	earthworks		
General	Submit a trial section of	5 working days prior to	Superintendent and Council
	stabilised earthworks	commencement of works	
General	Any deficient sections will	Progressive	Superintendent and Council
	require to be investigated		
	and may be directed to		
	remove		

Table SC6.4.5.3.55 Stabilisation-witness points

Clause/subclause	Requirement	Notice for inspection
Witness Points Off Site		
Materials		
Cement	Proof of quality and source	Progressive
Quicklime	Proof of quality and source	Progressive
Hydrated lime	Proof of quality and source	Progressive
Ground granulated blast furnace	Proof of quality and source	Progressive
slag		
Flyash	Proof of quality and source	Progressive
Blended stabilising agent		
Blended stabilising agent	Proof of quality and source	Progressive
—Standard		
Blended stabilising agent	Comply with supplier's handling and	Progressive
—Handling and storage	storage requirements and arrange	
	sampling of agent	
Witness Points On Site		
Quality Requirements—	Adjustment of Field Working Period for	Progressive
Compaction	site conditions	
Application of stabilising agent	Monitoring application of stabilising	Progressive
—Stationary mixing plant	agent at the plant	
Application of stabilising agent	Removal of spilled stabilising agent	Immediately upon spillage event
—Stationary mixing plant		
Application of stabilising agent	Actual spread to be recorded and	Progressive
—Spreading out	checked	
Application of stabilising agent	Record average spreading rate using	Progressive
—Spreading out	load cells	
Mixing—Stationary mixing plant	Test unconfined compressive strength	Progressive
Mixing—In situ mixing process	Visual inspection to ensure uniform	Progressive
	mixing and record	
Mixing—In situ mixing process	Additional passes of mixing equipment	Progressive
	to improve uniformity	
Trimming and Compaction—Survey	Survey to confirm pavement layer	Progressive
control methods	thickness remains within tolerances	
	after trimming	
Trimming and Compaction	Conform to surface tolerances prior to	As directed by Superintendent
—Straight edge test	sealing or practical completion of work	
	component	
Dimensions—Width	Random measurement of stabilised	As directed by Superintendent
	layer width	

Table SC6.4.5.3.56 Subsoil, foundation and pavement drains-hold points

Item/Clause title	Requirement	Notice for inspection	Release by	
Construction	Construction			
Subsoil and Sub-	Inspect excavated trench	1 working day prior to filling	Superintendent	
Pavement Drains /				
Foundation drains				
—Excavation				
Subsoil and Sub-	Present bedding of	3 working days before next	Superintendent	
Pavement Drains /	compacted filter material laid	activity		
Foundation drains—Laying	to line and grade			
of Pipes				
General—Filter material	Type of filter material	3 working days before	Superintendent	
		ordering material		
Intra-pavement drains	Provide certification that	3 working days before	Superintendent	
—Laying of pipe	drain has adequate crushing	ordering		
	strength			
Intra-pavement drains	Submit details of proposed	7 days before pipe laying	Superintendent	
—Laying of pipe	method of securing pipes			
Edge drains—Laying of	Submit details of proposed	7 days before pipe laying	Superintendent	
pipe	method of securing pipes			

Table SC6.4.5.3.57 Subsoil, foundation and pavement drains-witness points

Item/Clause title	Requirement	Notice for inspection
Construction		
Subsoil and Sub-Pavement Drains	Lay on compacted bed to documented	1 working day before filling
/ Foundation drains— Pipes	line and level	
Subsoil and Sub-Pavement Drains	Backfilling to documented level and	1 working day before covering with
—Backfilling	relative compaction	geotextile
Foundation drains—Backfilling	Backfilling to documented level and	1 working day before covering with
	relative compaction	geotextile
Geotextile—Installation	Placement of fabric conformance	1 working day before filling
Geotextile—Installation	Ensure exposure periods are within	Progressive
	the constraints	
Cleanouts—Field testing	Perform flushing test	Progressive (timing depending on the
		construction of pavement layers)

Table SC6.4.5.3.58 Subsurface drainage-witness points

Item/Clause title	Requirement	Notice for inspection	Release by	
General Control of the Control of th				
Siting of Work	Submit the proposed set-out in addition to the designed set-out	7 days before planned execution	Superintendent	
Siting of Work—Proposed changes	Present the proposed new set-out for approval	3 days before planned execution	Superintendent	
Excavation—Existing underground services	Submit evidence of approval of the relevant authorities.	14 days before planned excavation	Superintendent	
Excavation—Trenches	Approval of completed trenches required prior to installation of drainage work	1 working day prior to installation of drainage work	Superintendent	
Materials				
Subsurface drainage pipes—General	Submit compliance certificates	7 days before proceeding to provide pipes	Superintendent	
Other subsurface drainage pipes	Submit details of proposed alternative pipes and evidence of conformity for approval.	7 days before proceeding to provide pipes	Superintendent	
Geotextile—General	Provide documentation of conformity of geotextile and installation process	14 days before proceeding to provide geotextile	Superintendent	
Recording of drainage				
Recording of subsurface drainage Information	Progressive supply of subsurface drainage details	5 working days after completion of each drain or drainage system	Superintendent	

Table SC6.4.5.3.59 Subsurface drainage-witness points

Note—the Contractor must notify the Superintendent and/or council of impeding works, where the option of attendance may be exercised by the Superintendent and council.

Item/Clause title	Requirement	Notice for inspection
General		
Temporary drainage during	Locate materials and equipment clear	7 days prior to positioning
construction	of water courses	

Table SC6.4.5.3.60 Pavement markings-hold points

Clause title/subclause	Requirement	Notice for inspection	Release by	
General				
Material Quality	Submit NATA Test Reports on materials	7 days before work is scheduled to commence	Superintendent	
Surface preparation—Wet Weather	Superintendent direction on suspension of work	Progressive	Superintendent	
Removal of pavement mar	Removal of pavement markings			
General—Removal of redundant markings	Submit method for approval	working day before commencement of activity	Superintendent	

Table SC6.4.5.3.61 Pavement markings-witness points

Note—the Contractor must notify the Superintendent and/or council of impeding works, where the option of attendance may be exercised by the Superintendent and council.

Clause title/subclause	Requirement	Notice for inspection			
General	Seneral Control of the Control of th				
Setting Out—Net	Set out in accordance with the	Progressive			
	drawings				
Pavement marking paint					
Application of Paint Beads—Glass	Application method to be approved by	Progressive			
beads applied to other paint markings	Superintendent				
Field testing—Application Rate	Application to be checked for quality	Progressive			
Thermoplastic pavement marking m	naterial				
Field testing—Application Rate	Application to be checked for quality	Progressive			
Pavement marking tape					
Removal of Pavement Marking	Direction to remove pavement marking	Progressive			
Таре	tape				
Raised pavement markers					
Installation of Raised Pavement	Installation to be checked for quality	Progressive			
Markers	(allow adhesive to set)				

Table SC6.4.5.3.62 Guide posts-hold points

Clause/subclause	Requirement	Notice for inspection	Release by
General			
Materials—Proprietary	Supply details of the	Two weeks before	Superintendent
posts—Proposed supplier	proposed guide posts	manufacture	
Construction			
Erection of Guide Posts —Proprietary guideposts	Provide manufacturers anchorage instructions	5 working days	Superintendent
Erection of Guide Posts —Guide posts on concrete	Provide fixing details	5 working days	Superintendent
pavements			

Table SC6.4.5.3.63 Guide posts-witness points

Clause/ subclause	Requirement	Notice for inspection
Construction		
	Locations shown on drawings or as specified Check for existing underground services	Two weeks before installation
Erection of Guide Posts—Backfilling	Firm embedment in ground	Progressive
	Arrangement of delineators relative to traffic direction	Progressive

Table SC6.4.5.3.64 Signposting-hold points

Clause/subclause	Requirement	Notice for inspection	Release by
Materials			
General—Approved	Details of proposed suppliers	1 week prior to ordering	Superintendent
Supplier	provided to the		
	Superintendent including		
	documentary evidence		
General—Documentary	Evidence that materials and	1 week prior to engaging	Superintendent
Evidence	parts proposed comply with	supplier	
	the requirements of this		
	specification		
Retro-Reflective Material	Details of material and	1 week prior to ordering	Superintendent
for Background and	compatibility in application		
Legend	and durability		
Sign Support Structures	Details of proposed	2 weeks prior to fabricating	Superintendent
—Attachment of signs	attachment systems	attachment systems	
Erection of new signs			
Setting Out	Approval of the location and	1 week prior to erection	Superintendent
	alignment of the sign support		
	structure		
Setting Out—Existing	Locate services and protect	1 week prior to erection	Superintendent
underground services	against damage		
Special requirements			
Street Name, Service and	Submit details of	1 week prior to ordering	Council
Tourist Signs	manufacturer for approval by		
	council		

Table SC6.4.5.3.65 Signposting-witness points

Clause/subclause	Requirement	Notice for inspection	
Erection of new signs			
Setting Out	Submit details of and set out for each support structure	1 week before installing signs	
Clearing	Clear vegetation after set-out on advice from council	e 3 working days before clearing	
Sign Structure Footings —Excavation	Excavation as shown on drawings and as directed, including disposal of material	d 1 working day before next activity	
Erection—Sign Damage	Repair or replace damaged signs	1 week before installing signs	
Adjustment of existing signs and support structures			
General	Conform to Drawings and Superintendent direction	1 week before adjusting signs	

Table SC6.4.5.3.66 Non rigid road safety barrier system-hold points

Item/Clause title	Requirement	Notice for	Release by
		inspection	
Materials			
Certification—Evidence of	Provide documentary evidence of conformity	1 week prior to	Superintendent
Conformance	of steel components	erection	
Construction			
General— Set Out	Set out to drawings or as directed	2 working days prior	Superintendent
		to erection	
End Treatment of Road Safety	Submit alternative MELT locations	1 week prior to	Superintendent
Barriers—MELT		ordering	

Table SC6.4.5.3.67 Non rigid road safety barrier system-witness points

Note—the Contractor must notify the Superintendent and/or council of impeding works, where the option of attendance may be exercised by the Superintendent and council.

aperimendent and obtained.				
Item	Requirement	Notice for inspection		
Construction				
General—Sequence of Construction	Erection after pavement activities	1 week before installation –		
(pavements)		progressive		
General—Underground Obstruction	Alternative method due to obstructions	1 week before setting posts		
Erection of Steel Posts—Damage to	Assessment by Superintendent for	3 working days before removal of		
posts	replacement	damaged post		
Erection of Road Safety Barrier	Assessment and rejection by	1 working day after perceived damage		
Rails—Excessive damage to rails	Superintendent			

Table SC6.4.5.3.68 Minor concrete works-hold points

Clause/subclause	Requirement	Notice for inspection	Release by	
General Control of the Control of th				
Excavation and Foundation	Inspect prepared surface or	1 working day prior to	Superintendent	
General—Ground	sand underlay	covering		
preparation—Base				
preparation				
Excavation and Foundation	Inspect membrane or film	1 working days prior to	Superintendent	
General—Ground	underlay installed	covering		
preparation—Polymeric film				
underlay installation				
Approval of Formworks	Formwork design certificates	3 working days	Superintendent	
Design				
Erection—Formwork	Certification of installed	1 working day prior to	Superintendent	
	formwork and inspection	covering		
Materials for concrete				
Nominated Mix	Submit details of nominated	7 working days	Superintendent	
	mix for approval			
Reinforcement for concret	е			
Steel reinforcement	Inspect reinforcement	1 working day prior to	Superintendent	
placement—Approval of	placement	covering		
reinforcement before				
concrete placement				
Cores, fixings and	Shop drawings for cores,	7 working days prior to	Superintendent	
embedded items—General	fixings and embedded items	commencing works		

Clause/subclause	Requirement	Notice for inspection	Release by
	Approval for early loading of the structure by design	3 working days	Superintendent
	strength in situ tests		
Sprayed concrete general—	Submit proposal for spraying	14 days prior	Superintendent
Method statement			

Table SC6.4.5.3.69 Minor concrete works-witness points

Clause title/Item	Requirement	Notice for inspection
General		
Ground preparation—Mass	Inspect concrete blinding slab prior to	1 working day prior to covering
concrete bedding on earth foundations	placing forms or materials	
Concrete quality requirements	Check erection tolerances	1 working day
—Formwork		
Materials for concrete		
Certificate of compliance	NATA certificates for all materials	7 days prior to commencing on site
Handling and treatment of concrete		
Mixing of concrete—Hand Mix On	Submit proposal for use	7 days prior
Site		
Mixing of concrete—Pre-mixed	Submit delivery dockets and	Progressive
supply	subcontractors details	
Concrete quality requirements	Confirm unformed surfaces	1 working day
—Flatness		
Concrete quality requirements	Confirm surface quality	1 working day
—Surface quality		
Concrete curing	Certified test results for curing	7 days prior
	compound	
Joints	Submit proposal for sawn joints	7 days prior
Concrete placing and compaction	Certified test results for compressive	Progressive
—Testing	strength	
Reinforcement for concrete		
Steel reinforcement placement	Submit notice for test inspection	7 days
—Delivery and receipt of reinforcement		
Steel reinforcement placement	Submit proposed changes to	2 days prior to commencing on site
—Placing	reinforcement	
Steel reinforcement placement	Submit proposed repair method	2 working days prior
—Damaged galvanising		
Steel reinforcement placement	Submit proposed changes to spacing,	2 working days prior
—Provision for concrete placement	cover, splicing or welding or	
	reinforcement	
Cores, fixings and embedded	Approval for cutting or coring hardened	2 working days prior
items—Cutting or coring	concrete	
Sprayed concrete—Sprayed	Approval of sample panels	7 days
concrete test panel		

Table SC6.4.5.3.70 Boundary fencing-hold points

Clause title / item	Requirement	Notice for inspection	Release by		
Materials	Materials				
General—Material approval	Submit source, type,	One week before ordering	Superintendent		
	Certificate of compliance and	each type			
	manufacturer for eachtype				
	of material				
Construction					
General—Clearing and	Confirm approval for tree	One week before next	Superintendent		
grubbing	removal	activity			
Erection of posts					
Depth of posts	Method of installing and	One week before	Superintendent		
	proposed type of posts to be	manufacture or order			
	used				
Erection of wires—General	Approval for any proprietary	One week before	Superintendent		
	fasteners	manufacture or order			
Flood gates—General	Approval to proceed with	One week before fabricating	Superintendent		
_	flood gates and type	flood gates			
Removal and disposal of	Approval required for burn off	Prior to burning	Superintendent		
	for combustible materials	-			
rubbish					
Bedding—Cattle Grids	Approval for bedding	One week before fabricating	Superintendent		
	requirements	flood gate			

Table SC6.4.5.3.71 Boundary fencing-witness points

apolitici della codicia.					
Item	Requirement	Notice for inspection			
Materials	Materials				
Galvanised Posts, Braces and Rails	Welding sites to be cleaned and	Progressive			
—Welded Joints	painted				
Gates—Dimensions and Fittings	Fitting alternatives	3 working days before fabrication			
Construction					
Stock-Proof Fencing—Erection of	Posts sunk to the required depths	Progressive			
posts—Depth of posts					
Crossing of Watercourses and	Secure by installing longer posts as	Progressive			
Depressions	directed				
Flood gates—Small water courses	Provide required waterway area	Progressive			
Erection of Gates	Double gates to be directed	One week before ordering			
Removal and disposal of surplus	All surplus material to be removed	Progressive			
material and rubbish					

Table SC6.4.5.3.72 Control of traffic-hold points

Requirement	Notice for inspection	Release by
<u> </u>		
Approval of Traffic guidance	2 weeks before proposed	Superintendent.
scheme	commencement on site	
Provide evidence of	4 weeks before proposed	Superintendent
approvals from Council and	commencement on site	·
other Authorities		
Carry out a risk assessment	4 weeks before proposed	Superintendent.
for works not involving	commencement on site	
complex TGS or staged		
works		
Provide Proposal for access	5 working days prior to	Superintendent.
·		
	, 0	
Approval to deny vehicular	3 working days prior to	Superintendent.
property owners	, ,	
detours		
Submit design of all	5 working days prior to	Superintendent.
proposed temporary	carrying out works	
roadways and detours		
Present completed	5 working days prior to	Superintendent.
temporary roadways and	carrying out works	
detours to the		
Superintendent for approval		
prior allowing traffic		
Approval required to	3 working days prior to	Superintendent.
construct under traffic	carrying out works	
Submit full details of	5 working days prior to	Superintendent.
temporary signposting, traffic	carrying out works	
control devices and traffic		
control methods for approval		
Provide written notice to the	5 working days prior to	Superintendent.
Superintendent confirming	opening of completed works	
date of opening of completed		
works.		
Rectify inadequate traffic	1 working day of notice	Superintendent.
control devices		
	Approval of Traffic guidance scheme Provide evidence of approvals from Council and other Authorities Carry out a risk assessment for works not involving complex TGS or staged works Provide Proposal for access Approval to deny vehicular access and provide notice to property owners detours Submit design of all proposed temporary roadways and detours Present completed temporary roadways and detours to the Superintendent for approval prior allowing traffic Approval required to construct under traffic Submit full details of temporary signposting, traffic control devices and traffic control methods for approval Provide written notice to the Superintendent confirming date of opening of completed works. Rectify inadequate traffic	Approval of Traffic guidance scheme commencement on site Provide evidence of approvals from Council and other Authorities Carry out a risk assessment for works not involving complex TGS or staged works Provide Proposal for access Provide Proposal for access 5 working days prior to carrying out works Approval to deny vehicular access and provide notice to property owners Idetours Submit design of all proposed temporary roadways and detours Present completed temporary roadways and detours to the Superintendent for approval prior allowing traffic Approval required to construct under traffic submit full details of temporary signposting, traffic control methods for approval Provide written notice to the Superintendent confirming date of opening of completed works. Rectify inadequate traffic 1 working day of notice

Table SC6.4.5.3.73 Control of traffic-witness points

Note—the Contractor must notify the Superintendent and/or council of impeding works, where the option of attendance may be exercised by the Superintendent and council.

Clause/Item	Requirement	Notice for inspection by the Superintendent			
General	General				
Traffic Guidance Scheme (TGS)	A copy of the approved Traffic	Progressive			
—Site Copy	Guidance Scheme must be kept on site				
Traffic Guidance Scheme—Safety	For complex traffic arrangements and	Progressive			
Audit	staged works carry out safety audits				
Traffic Controllers—Personnel	Submit names and declaration of	Prior to commencing work			
	proposed traffic controllers				
Temporary Speed Zoning—Record	Diary and method of works	Progressive			
Temporary roadways and detours	Temporary roadways and detours				
Drainage—Pavements	Pavement designed and constructed	Progressive			
	not to pond water				
Surfacing—Extent	Width of wearing surface and position	3 working days prior to carrying out			
	of finish tying into existing works	works			
Traffic control devices					
Arrangement of traffic control	Arrangement and placement as per	Progressive			
devices	the approved TGS				
Temporary markings—Line Marking	Ineffective line marking, remark within	Progressive			
	48 hours.				
Temporary markings—Old Markings	Obliterate or remove old markings.	Progressive			
Removed					
Raised Pavement Markers	Replace ineffective markers within 24	Progressive			
—Ineffective Markers	hours.				

SC6.4.5.3 Attachment E Non conformance Certificate (NCC) - Template

Click here to obtain a copy of the following form.

SC6.4.5.3 Attachment F Non Conformance Report (NCR) - Template

Click here to obtain a copy of the following form.

SC6.4.5.3 Attachment G Notice of Non Conformance Report (NNC) - Template

Click here to obtain a copy of the following form.

SC6.4.5.3 Attachment H Corrective and Preventive Action Request (CPAR) - Template

Click here to obtain a copy of the following form.