


**NOTES**

1. All dimensions are in metres unless noted otherwise.
2. This drawing to be read in conjunction with Development Manual, relevant Australian Standards and manufacturer's specifications.
3. Wearing surface, pavement design and subgrade treatment to be in accordance with Development Manual SC6.4.4.2 Pavement Design.
4. Wearing surface in highly stressed areas due to braking, turning and acceleration, such as roundabout and stopping lanes at traffic signals, shall be polymer modified asphalt as per Main Roads Technical Specification 18 – Polymer Modified Binder.
5. Subsoil drains to be in accordance with Development Manual SC6.4.4.2 Pavement Design and TCC Standard Drawing SD-080.
6. For principles underlying street/road selection and network planning refer to Development Manual SC6.4.4.1 – Geometric Road Design.
7. For street lighting requirements refer to AS1158.
8. Pavement marking and RRPm's to be in accordance with Main Roads MUTCD – Part 2.
9. Location of all existing services shall be confirmed by the relevant authority prior to commencement of any construction works.



**SUB ARTERIAL TYPE A  
KERBS AND UNDERGROUND DRAINAGE**

- Posted speed 80km/h
- No on-street parking provision
- Provision for bus route if required (no bus stop permitted)
- Lane lines and edge lines to be shown on layout plan
- Footpath to be provided as per footpath network plan for development


Refer to Development Manual SC6.4.4.1 Geometric Road Design and SC6.4.3.13 Townsville Road Hierarchy

■ Minimum Road Reserve Width and Verge Widths dependent on pathway requirements. Refer TCC Standard Drawing SD-015.

⊗ Bicycle lane widths shown are desirable minimums. Refer to Austroads Guide to Road Design Part 3: Geometric Design (Table 4.17)

**WEARING SURFACE AND PAVEMENT DESIGN**

∅ Wearing surface (minimum depth of 50mm asphalt) and pavement design to be determined by the Design Engineer. Refer notes 3 and 4.



**SUB ARTERIAL TYPE B  
NO KERB AND VERGE DRAINAGE**

- Posted speed 80km/h
- No on-street parking provision
- Provision for bus route if required (no bus stop permitted)
- Lane lines and edge lines to be shown on layout plan
- Footpath to be provided as per footpath network plan for development


Refer to Development Manual SC6.4.4.1 Geometric Road Design and SC6.4.3.13 Townsville Road Hierarchy

No.	DATE	DESCRIPTION	AP'D
B	29/04/2014	AMENDMENTS FROM DEVELOPMENT MANUAL CONSULTATION	
A	08/2013	ORIGINAL ISSUE	
REVISIONS			

NOTES :

Full Size A1  
Not to Scale

DRAWN: DESIGN OFFICE  
CHECKED: WP  
Design Engineer Approved: Original signed by JORGE EL-KHOURI  
Date: 28/5/14  
Manager Approved: Original signed by JOHN CLARKE  
Date: 28/5/14



TYPICAL CROSS SECTIONS  
SUB ARTERIAL ROADS

STANDARD DRAWING  
ROADWORKS  
SD-003 B